# FE311

Diagram No. 5531-1

NOAA FORM 76-35A

U.S. DEPARTMENT OF COMMERCE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION
NATIONAL OCEAN SERVICE

# DESCRIPTIVE REPORT

Type of Survey Field Examination

Field No. PHP-10-4-87

Registery No. FE-311

LOCALITY

State California

General Locality San Francisco Bay

Sublocality Southern Portion of

San Francisco Bay

1987

CHIEF OF PARTY
LT F.R. Diaz

LIBRARY & ARCHIVES

☆U.S. GOV. PRINTING OFFICE: 1985-568-054


November 28, 1988

18659 1 med, 40,000/80000

NOAA FORM 77-28 (11-72)	U.S. DEPARTMENT OF COMMERCE NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION	REGISTER NO.	:
	HYDROGRAPHIC TITLE SHEET	FE-311	

INSTRUCTIONS - The Hydrographic Sheet should be accompanied by this form,	FIELD NO.
filled in as completely as possible, when the sheet is forwarded to the Office.	PHP 10-4-87
State California	
General locality San Francisco Bay	
Locality Southern Portion of San Francisco Bay	
Scale 1:10,000 Date of surv	vey 04 to 16 November 1987
Instructions dated February 10, 1987 Project No.	OPR-L123-PHP-87
Vessel Launch 1101 (EDP 0651), Whaler (EDP 065	4)
Chief of party LT F.R. Diaz	
Surveyed by LT F. Diaz, LTJG T.K. Porta, LTJG E.A. SURVEY TECH M.E. Bigelow	Crozer, ENG TECH B.H. Lund,
Soundings taken by echo sounder, hand lead, pode Pneumatic Pr	essure Gauge
Graphic record scaled by PHP Personnel	
Graphic record checked by F.R. Diaz, T.K. Porta	
Evaluated by: C.R. Davies Automat	ted plot by PMC Xynetics Plotter
Verification by R.N. Mihailov	
Soundings in factions feet at MKWX MLLW	
REMARKS: Revisions and marginal notes in black gener	ated during office
processing. Separates are filed with the h	ydrographic data.
- AWOIS and SURF 5/89 R	ND .






DUMBARTON BRIDGE EAST FENDER

11/11/87

DUMBARTON BRIDGE
EAST FENDER 11/11/87

EAST LOOKING WEST



DUMBARTON BRIDGE WEST FENDER

11/11/87



DUMBARTON BRIDGE WEST FENDER 11/11/82

WEST LOOKING EAST



Pos. 373 and 381




Pos. 380





Pos. 678



# DESCRIPTIVE REPORT TO ACCOMPANY HYDROGRAPHIC SURVEY EE 311, FIELD NO. PHP-10-4-1987 Scale 1:10.000, Year 1987 Pacific Hydrographic Party Chief of Party: LT Fred Diaz

### A. PROJECT.

A field examination was performed in accordance with Project Instructions OPR-L123-PHP-87, dated February 10, 1987, and Change No. 1 dated March 20, 1987. These Project Instructions encompass all of San Francisco and San Pablo Bays.

The field examinations were conducted within the limits of chart 18651. The items investigated were unresolved from basic surveys H-9819, H-9872, H-9952, H-9984, and H-10132 used to update Chart 18651. The following items from the office review, dated October 25, 1984 (given a priority one or two rating), have been completed: 160, 161, 166, 167, 168, 169, 170, AWOIS 50781, 50782, and 51147 (188).

Due to time constraints set forth by the project instructions, the following items (given a lower priority rating) were not resolved: 150, 151, 152, 163, 164, 165, 171 and AWDIS 50785.

### B. AREA SURVEYED.

The investigations were performed in south San Francisco Bay, CA, from Oyster Point south to Dumbarton Point. The dates of the survey were from O4 to 16 November (DN 308-320). The survey limits were:

Lat. 37/41/00 N to 37/29/00 N Long. 122/24/00 W 122/06/00 W.

The southern portion of San Francisco Bay has heavy traffic from deep drafted vessels to shallow draft pleasure craft. The main channel and Redwood creek are maintained by the U. S. Army Corps of Engineers. The Brisbane, Oyster Cove, Oyster Point, and Coyote Point marina entrances are privately maintained and mainly used by privately owned small vessels and a few small commercial vessels.

# C. SQUNDING YESSEL.

PHP's Launch 1101 (EDP 0651), was used as the vessel for all data acquisition, bottom drags, and dive investigations.

The vessel is a 29-ft aluminum hulled Jensen launch powered by a turbo charged 3208-T Caterpillar diesel engine and a Hamilton jet drive unit.

PHP 17-ft Boston Whaler (EDP 0654), powered by twin Evinrude 25-hp outboards, was used for wire drag operations as a tow boat only.

### D. SOUNDING EQUIPMENT.

Launch 1101 is equipped with a standard Ross Fineline echo sounder and digitizing system which utilizes a centerline mounted, 7.5 degree, 100 KHz transducer. Launch 1101 is also equipped with two side looking digital transducers for navigational use in sloughs, narrow channels, and creeks. The Ross system on launch 1101 consists of the following instruments:

Component	Model No.	SZN
Power Inverter	2000	1071
Transceiver	4000	1081
Analog Recorder	5000	1080
Digitizer	6000	3787

Leadline PHP-1, and pneumatic gauge (S/N 8604205N) were used on item and diver investigations. Final field sheet soundings were corrected for leadline and pneumatic depth gage calibration (where appropriate). The pneumatic depth gauge was calibrated once daily when performing diver (least depth) investigations as stated in Hydrographic Survey Guideline #55.

### Sounding Instrument Accuracy and Adjustments.

The Ross echo sounding system simultaneously produces an analog echogram and a digitized depth value. Digitized soundings sampled by the logging system at predetermined time intervals are the primary source of sounding line data on the field sheet, but these are supplemented by depths scaled from the analog record in areas where digitized depths were incorrect or lacking. The digitized depths are sometimes triggered by a source other than the bottom (sea weeds, fish, etc.) or from an instrument generated source such as side echos. In these instances the digitized depths were replaced by values scaled from the echogram.

Initial error occurs when the echo sounder's transmit pulse trace is not adjusted to coincide with the zero on the echogram paper. The initial trace alignment was monitored and adjusted during survey operations. Any depths scaled from echograms with initial error were corrected before being applied to the survey.

Phase errors are caused by faulty stylus belt timing in the analog recorder due to belt stretching or improper internal adjustment. The system was checked for phase error at the beginning of each survey day and, with few exceptions, at the end of each survey day (or whenever the analog paper was changed) by introducing simulated depths (e.g. 10 ft, 20 ft, 30 ft, etc.) into the analog recorder via the digitizer phase calibration mode. The analog trace was then compared to the simulated digital depth and the equipment was adjusted as necessary.

The analog's speed had no inconsistencies on this survey.

### Static Transducer Draft.

The static transducer draft values for the hull mounted transducer on Launch 1101 was physically measured in two parts. The first part was done while the launch was out of the water. The distance between the transducer face and the bottom of a black line painted on the hull above the water line was measured using a surveying level (Lietz B-1, 5/N 214303) and rod. The second part was done with the launch in the water with a normal fuel load on board. The distance between the bottom of the painted black line and the actual water line was measured with a steel tape.

The actual static transducer depth is the distance obtained in part 1 minus the distance measured in part 2. The actual static draft was measured at 1.63 feet.

### Sound Velocity Correctors.

Observed depths on this survey ranged from 0 to 50 feet. Sound velocity correctors were derived from bar check data. Bar checks were made once daily, when soundings were obtained.

Before the project commenced, the standard bar for PHP was lost while performing operations (DN 295). To save time and money, PHP requested a replacement bar from PMC, Seattle, WA. The bar sent from PMC was a cast iron grate (6.0 ft x 1.5 ft) which had a smaller length than the PHP standard bar. The location on the deck of the launch where bar checks are performed is 11.25 ft (full beam) between the two chain holders. The line depth was less than what the chain markings (5 to 50 ft) registered, since the chains were scoped inward, toward the hull instead of being straight up and down while performing bar checks. The scoping of the marked chains occurred mostly at the 5- and 10-ft chain markings. As the bar was lowered, the chains became more straight up and down. Line correctors were computed for each chain marking and applied to the bar check data. Results are included in Appendix IV of this report.

\* filed with hydrographic data

A sound velocity curve was calculated from the bar check data. The mean and standard deviation was computed for each depth corrector to identify blunders or suspicious data. Since there were so few bar checks on this survey all the data was retained. The overall corrector values for depths were plotted on a depth versus velocity corrector graph. From this graph a line was drawn through the points and a table of correctors was determined. The following table is appropriate for the dates shown:

Table

Inclusive Dates (Year days)

I

308/87 - 320/87

Sounding data was acquired during most of the bottom drag operations. This information was acquired for the launch crew to facilitate drag operations and should not be used for charting purposes since bar checks were not performed.

Sounding data was included on the smooth check Settlement and Squat Corrections.

The digital speed log for Launch 1101 was originally acquired in April, 1984 to test for ground effect, which is the change in speed when moving to and from shallow water (see Ground Effect Report, May, 1984). From this testing it was determined that one method to help reduce the need for ground effect correctors was to operate the launch by constant speed through the water instead of fixed rpm. This decision was cleared through FMC and the speed log was permanently mounted in the hull of Launch 1101. All soundings collected with Launch 1101 were annotated as to speed through the water, not rpm. Speed through the water was likewise used during the settlement and squat tests.

Settlement and squat measurements were observed for the Pacific Hydrographic Party's Launch (EDP 0651), an aluminum Jensen survey launch, on April 7, 1987 (DN 97). This test was conducted during survey operations on OPR-L123-PHP-86 and OPR-L123-PHP-87. The settlement and squat correctors apply to all data acquired on this survey.

Equipment on the launch at the time of the test consisted of normal electronic positioning and depth finding gear (Mini-Ranger, HDL system, Ross echo sounder). The launch is equipped with a Caterpillar Diesel engine coupled to a jet pump. Three people were on board the launch at the time of the test (a normal crew for surveying).

The test was conducted between the General Mills pier ruins (38/04/50 N and 122/14/50 W) and Mare Island Strait Light 4. The test was in the limits of OPR-L123-PHP-86. The launch went from depths of 20 to 40 feet of water. The weather during the test was calm, with winds 0 to 5 kts, seas were calm and the current was slack.

The level was set up on stable pier ruins at the General Mills flour company, Vallejo, California. A level rod was held on the cabin top, over the position of the hull mounted transducer. The launch was driven towards the instrument man on the pier, stopping for dead in the water (DIW) measurements before and after each run.

The Pacific Hydrographic Party uses a speed log rather than rpm to measure vessel speed during hydrographic operations. Settlément and squat measurements were acquired for all speeds of hydrography.

Changes in transducer draft due to settlement and squat were measured at regular intervals through the range of 3 nm/hr to 10 nm/hr. These point values were plotted and connected to yield continuous speed versus draft correction curves.

Settlement and squat corrections are not applied to the field sheet, but are incorporated on the TC/TI tapen ses correctors were officed to the smooth sheet.

For predicted tide correctors for each item investigated, refer to the Field Tide Note, Appendix II (affacked)

Correctors Applied to the Paper Plots and Expansion Sheets.

Launch 1101

Predicted tide correctors Static Draft correction

Pneumatic gage

Pneumatic gage correctors Predicted tide correctors

PHP-1 leadline

Leadline correctors

Predicted tide correctors

Correctors Applied to the Final field Sheet.

Launch 1101

Predicted tide correctors Static Draft correction Sound velocity correction

Pneumatic gage

Predicted tide correctors

PHP-1 leadline

Leadline correctors Predicted tide correctors

# E. HYDROGRAPHIC SHEETS.

Five 1:10,000-scale field sheets, two 1:5000-scale and three 1:2500-scale expansion sheets were constructed by PHP members with program RK 201 on a Modified Transverse Mercator projection using a Houston Instruments Complot DP-3 flatbed plotter.

The expansion sheets were constructed to show better depth delineation for features on Items 166, 168 and the entrance to Brisbane Marina.

Field records were forwarded to the Pacific Marine Center, Nautical Chart Branch, Seattle, Washington, for verification and smooth plotting, as arranged by both PHP and PMC (N/MOP21), due to time constraints and the lack of a full compliment of personnel on PHP.

# E. CONTROL STATIONS.

Control stations used on field examinations are:

NEW POSITION OR VERIFICATION OF OLD	STATION	LOCATION METHOD
Verified by PHP	DUMBARTON DRAWBRIDGE	Traverse
11 'S	DUMBARTON PG E WEST TOWER LT, 1983	н
н	KGO RADIO STATION CENTER MAST, 1982	
Positioned by PHP	OAKLAND TRIBUNE BLDG FLAG ECC,	) ii
Verified by PHP	8L06 <del>DUILDING</del> 253, 1948	п
II.	POINT SAN BRUND, 1925	;
H	SIERRA POINT, 1851	11
	OYSTER POINT MARINA	H.
<b>n</b>	DYSTER POINT MARINA	u
	COYOTE POINT YACHT H	ARBOR "
n.	POINT SAN MATEO, 1925	11
U	SAN FRANCISCO BAY S CH LT 14, 1983	II
	HETCHY, 1983	и
	RED HILL TOP, 19 <del>50</del>	11

All stations were positioned to Third Order, Class I, or better accuracy. Geodetic computations were based on the 1927 North American Datum. For more information see the Horizontal Control Report, San Francisco Bay and San Pablo Bay, CA., OPR-L123-PHP-87 dated March, 1987 to October, 1987 (submitted to PMC for verification) and Horizontal Control Report, South San Francisco Bay, CA., OPR-L123-PHP-87, which will be submitted for verification upon completion of the project.

# G. HYDROGRAPHIC POSITION CONTROL.

Electronic launch position control on these investigations were accomplished with a Motorola Mini-Ranger III ultra-high frequency transponder system in the range-range or range-azimuth configuration. Sextant-sextant methods were used as checks on the above methods.

### Electronic Control Equipment.

The following electronic positioning equipment were used on this survey:

### Motorola Mini-Ranger III Mobile Station Launch 1101

Mini-Ranger Console S/N 701 Transceiver (RT Console) S/N 1081

# Motorola Mini-Ranger III Reference Stations

Mini	Ranger	Transponder,	Code	Α	S/N	F3233
		Transponder,			S/N	911059
Mini	Ranger	Transponder,	Code	С	S/N	E2712
Mini	Ranger	Transponder,	Code	7	S/N	4709

# Position Control Equipment Operation.

Baseline calibrations for data collected on this survey were performed September 29 (DN 272) and December (DN 357) 1987 over a slope distance of 777.7 meters at Benicia, CA.

# Corrector/Minimum Signal Strength

Date of BLC	Code	Code	Code	Code	Applicable
	A	B	C	7	Dates
September 29, 1987 December 23, 1987	-2/8 -2/9			0/11 -4/8	308-320

PHP is adhering to a two to three month baseline calibration schedule. Daily critical systems checks confirm that the Mini-Ranger correctors determined from the September 29 baseline are valid for the entire survey.

There were no positioning equipment failures during these investigations.

Daily Calibrations.

Critical system checks were performed once each day at a geodetic monument. All daily system checks on the Mini-Rangers and console/RT unit during this time period resulted in a variance of less than 5 meters. PHP considers these system checks a confirmation of the BLC and proper Mini-Ranger operation.

Fixed aids to navigation (located to Third Order Class I standards) used for calibration were:

OYSTER POINT MARINA LT 1
OYSTER POINT MARINA LT 2
COYOTE POINT YACHT HARBOR LT 1
SAN FRANCISCO BAY S'CH LT 14

The observed distances were corrected for antenna offset and were compared with the computed slope distance to yield the observed system corrector. The observed system corrector was then compared with the BLC and required to be within 0.5 millimeters at the scale of the survey. All hydrographic data meets this requirement.

The geometric configuration of the control stations and the signal strengths for all positions were good. Angles of intersection for all survey data were between 30 and 150 degrees. Signal strength was annotated on the raw data printout frequently during sounding acquisition. No data was submitted with less than minimum signal strength.

There were no unusual methods of electronic control operations, and no unusual atmospheric conditions on these item investigations.

The theodolites used for range-azimuth control were Wild T-2, S/N 276812 and S/N 35797.

The EDMI used for these investigations was a Kern DM 102, SN 293684.

### **EQUIPMENT FAILURES**

There were no equipment failures.

For further information on electronic calibrations see \*Appendix V, of this report.

\* filed with the hydrographic data

H. SHORELINE.

Shoreline verification was conducted by the hydrographer for all shoreline within the search radii of the investigations. There were no changes to the shoreline.

The following stations are seaward of the shoreline:

STATION	NUMBER
OYSTER POINT MARINA  LT 1, 1979 (pile)	641
OYSTER POINT MARINA	642
COYOTE POINT YACHT HARBOR-LT 1,1980	643
SAN FRANCISCO BAY S CH LT 14, 1983 (pile)	645

### I. CROSSLINES

When comparing the crosslines to the main scheme, there is a 100 per cent (100%) agreement of 0 to 1 ft. These discrepancies may be due to the irregular bottom and use of predicted tides in lieu of real tides. The following items contain crosslines:

IIEM	Z CROSSLINES	Mainscheme vs <u>Crossline FT</u>
166	, 10 · 5	0
167	15	Ö
168	20	O
188	50	Ö

This comparison is considered good and meets the comparison criteria specified in Section 4.6.1 of the <a href="https://example.com/html/>
MANUAL.">HYDROGRAPHIC</a>

# J. JUNCTIONS.

Not applicable as stated in the project instructions.

See Eval Rpl Sect 5

### K. PRIOR SURVEYS.

Not applicable as stated in the project instructions. See Section L below.

### L. COMPARISON WITH THE CHART.

See Eval Rpt Sect 7

The items on this survey were compared to chart 18651 35th ed. July 5, 1986.

# DANGERS TO NAVIGATION

Two Dangers to Navigation letters were written to the Commander, Eleventh Coast Guard District, concerning the submerged obstructions observed on this survey. A copy of these letters are included in Appendix XII, Dangers To Navigation. A copy of these letters were also sent to the Chart Information Section, N/CG222, and Nautical Chart Branch, N/MOP21. These letters are dated 23 November 1987 and 16 December 1987.

CHART 18651 Description	Latitude	(NAD	Longitude 1927)	Lea	st Depth (MLLW)	POS
Submerged Obstruction	37/39/56.9	φ Ø N	122/22/47.20		-8.0 ft	2205
Submerged Obstruction	37/40/06.7	1 N	122/22/55.46		-7.0 <del>-6.6</del> ft	2384
Submerged Obstruction	37/40/06.4	0 N	3 122/22/54.4 <b>½</b>	₩	-3.0 <del>-8.6</del> ft	2385
Submerged Obstruction	37/35/00.5	7 <del>0</del> N	45 122/14/58. <del>20</del>	W	o 46. <del>6</del> ft	2723
Submerged Obstruction	37/35/00.8		19 122/14/59.4 <del>0</del>		28.0 <del>37.3</del> ft	2722
Scidge Submerged Ruins			ct portion)			
from to	37/30/24.3	2 N	122/06/56.57	W	•	2732 2737
In the vicinity	J'ME THMM 1.	LA 1				

In the vicinity of Item 160, two submerged obstructions were observed (refer to Dangers to Navigation Letter dated 23 November 1987) in Appendix XII), at position number 2384, and 2385 on DN 311, 7 November 1987. These dangers to navigation were observed near the entrance channel to Oyster Cove and Brisbane Marinas at 37/40/06.71 N, 122/22/55.46 W, and 37/40/06.40 N, 122/22/54.42 W with least depths of -6.6 -7.0 ft and -8.6 ft, respectively. Both submerged obstructions are stacked chunks of cement reinforced with rebar (rip-

rap). It is recommended that these dangers to navigation be charted at the above geographic positions.

Ruins exist east and west of the main shipping channel, within the area common to where the "old" Dumbarton Bridge existed prior to its demolition in 1985. Refer to Dangers to Navigation Letter dated 16 December 1987, in Appendix XII and this section under AWOIS Item 51147 (188) for charting recommendations.

The harbor master, Brisbane Marina, Brisbane, CA informally requested that PHP check the controlling depths of the privately maintained entrance channel near Brisbane Marina (Sierra Point); and Oyster Point Marina at 37/40/15 N and 122/22/30 W, as local boat owners felt the charted controlling depths of 4 ft at 37/40/15 N, 122/22/30 W and 2 ft at 37/40/10 N, 122/23/00 W were in error on chart 18651 35th ed., July, 1986.

As a token of our appreciation for free moorage and use of facilities, PHP performed one centerline and two side channel lines (positions 2318-2398) in the entrance channel, while performing item investigations.

The controlling depth (using predicted tides and velocity table 1) is 7 ft throughout the entrance channel. A paper copy of the midchannel survey was submitted to the harbor master, Brisbane Marina and a coveryletter dated 19 Jan 1988. A copy of this letter is included in Appendix XIII. The Harbor master was informed that the data was preliminary information and subject to further verification.

Chart the 7-ft depth as the controlling depth.

See Eval Rpt Sect 7.c.

### ITEM INVESTIGATIONS

All charting recommendations are based on MLLW from predicted tides (for a complete list of corrections see Section D) measured in feet (ft). Elevations and depths may change when smooth tides are applied.

All times are Universal Coordinated Time (UTC).

Inverse distances were calculated from the detached position to its check position. These distances are in meters (m) and are located in the cahier under their respective day numbers.

The following method was used for circle bottom drag investigations. A 50-lb weight with a float was attached to a 100-m, 5/8-in diameter nylon line. A 10-lb weight was attached to the line 30 meters from the 50-lb weight. A 25-lb weight was attached to a second line 70 meters from the middle 10-lb weight. A 25-m tow line was attached to the

25-1b weight. Two circles were made in one direction, then the launch was pulled to the center weight to check for hangs near the center of the search. Then two circles were driven in the opposite direction and the launch was again pulled to the center weight to check for hangs. The launch speed was adjusted to ensure the weight was on the bottom. If a hang was observed during the drag, divers would investigate by diving down the hang line (see drag set up, Figure 1, Appendix XIII).

Diver investigations in the entire San Francisco Bay area are difficult to perform since:

-Zero visibility water prevents divers from acquiring a full description of the submerged item being investigated.

-Treacherous currents (2 to 3 kts are common) preclude dive operations, especially in the south bay. There is essentially no slack current in the area around the San Mateo-Hayward and Dumbarton Highway Bridges.

CHART: 18651 35th ed. July 5, 1986

ITEM: 160

(Sheet 5

ITEM DESCRIPTION:

Submerged Piles and Dolphins

SOURCE: H-9819/79

DATE	DN	POSITIONS	TIME	VESNO
11/05/87	309	2041-2058	1822-1919	0651
11/06/87	310	2150-2159	1829-1859	

OȚC: LT Diaz LTJG Porta

GEODETIC POSITION	Latitude N	Longitude W	POS
Charted:	37/40/09.00	122/22/42.80	
Search:	37/40/09.09 37/40/11.99	122/22/42.72 122/22/42.56	2041 2150

### POSITION DETERMINED BY:

Mini-Ranger (range-range, with check)

### METHOD OF INVESTIGATION:

A 100-m radius circle drag was performed around the charted position of Item 160 (positions 2041-2058). At positions 2051 + 2 and 2055 + 3, stray soundings within the drag area were noted on the echogram. No significant hangs were observed on this day.

On DN 310, a 100-m radius bottom drag was performed to investigate the stray soundings mentioned above (2150-2159). Position 2150 was the center of the drag with an inverse distance of 0.3 m. No significant hangs were observed.

### CHARTING RECOMMENDATION:

Delete "submerged pile" symbol from the chart.

CONCUR

18651 - Deleted "Submpile 11-3-59 P 18652 Deleted " 11-6-64 P CHART: 18651 35th ed. July 5, 1986 ITEM: 162 (Sheet 5.45)

ITEM DESCRIPTION: Pile

SOURCE: H-9819/79

<u>DATE</u> <u>DN</u> <u>POSITIONS</u> <u>TIME</u> <u>VESNO</u> 11/05/87 309 2059-2099 1948-2219 0651

OIC: LT Diaz LTJG Porta

GEODETIC POSITION		Latitude N	Longitude W	POS	
	Charted:	Pile	37/40/04.50 37/40/05.00	122/23/15.00 * 122/23/13.54 *	
		11 · · · · · · · · · · · · · · · · · ·	37/40/05.80 37/40/08.50 37/40/09.20	122/23/10.48 122/23/06.90 * 122/23/06.40 *	
	Search:	. 4	37/40/04.77 37/40/06.05 37/40/08.40	122/23/13.54 122/23/10.48 122/23/06.26	2059 2074 2089

# POSITION DETERMINED BY:

Mini-Ranger (range-range, with check)

# METHOD OF INVESTIGATION:

The position of the five piles in the vicinity of 37/40/06.8 N, 122/23/03.4 W were scaled from the chart. Three 100-m radius bottom drags were required to cover the 30-m radius area around each of the five charted piles. The inverse distances for the positions 2059, 2074, and 2089 are 2.87 m, 3.40 m, and 4.38 m respectively. In some areas, non floating aids to navigation were within the radius of the drag. The launch coxswain avoided tangling the drag line by manuevering around them. To the best of ones ability, the coxswain continued to perform a 100-m radius circle drag.

No significant hangs were observed.

# CHARTING RECOMMENDATION:

Delete charted piles listed above.

18651 - Deloted 5 different o Piles 11-3-59 AP
18652 - Orligin 4 different o 11-6-59 AV

CHART: 18651 35th ed. July 5, 1986 ITEM: 166 (5heat 1045)

ITEM DESCRIPTION: Discontinued spoil area

SOURCE: H-9952/81-82

<u>DATE</u> <u>DN</u> <u>POSITIONS</u> <u>TIME</u> <u>VESNO</u> 11/06/87 310 2229-2317 2121-2256 0651 11/07/87 311 2399-2496 1845-2141

OIC: LT Diaz LTJG Porta

Charted: 37/39/00 122/22/24
Observed: 5 37/39/13.2 122/21/50.19 2496

### POSITION DETERMINED BY:

Mini-Ranger (range-range, with check)

### METHOD OF INVESTIGATION:

Forty-five-meter spaced lines were performed (positions 2229-2450) to develop the "discontinued spoil area" at the above charted location. Two crosslines (positions 2451-2470) were performed to check the mainscheme lines. A shoal was observed at position 2441 + 2.5. A 10-m spaced development (pos 2471-2496) was performed to delineate the extent of this shoal. A lead line least depth and bottom sample (Brk sh, sand) were acquired at position 2496 at the above location. The least depth is 10.2 ft in approximately 12 to 13 ft of water.

No indication of spoil area was observed. Comparison with the chart is excellent in the area. One hundred percent (100%) of the soundings agree within 1 ft.

# CHARTING RECOMMENDATION:

Delete "discontinued spoil area" from charted position. ..... cowor

Chart 10-ft least depth at the observed position.

Survey depths supersede all prior surveys and charted depths in the area.

Allready done in 12/88 P

15C52 Deleted Sport Area 11-6-84 P

167 (Sheet 5.85) 18651 35th ed. July 5, 1986 ITEM:

ITEM DESCRIPTION: Discontinued spoil area

**SOURCE:** H-9952/81-82

\_DATE\_ DN POSITIONS TIME **VESNO** 11/06/87 310 2160-2228 1923-2052 0651

OIC: LT Diaz LTJØ Porta

GEODETIC POSITION Latitude N Longitude W POS

Charted: 37/39/54.QQ 122/22/30.00

Observed: ( 37/39/56.94 122/22/47.13 2205

(-8.0 ft <del>subm</del> obstruction)

# POSITION DETERMINED BY:

Mini-Ranger (range-range, with check)

### METHOD OF INVESTIGATION:

Forty-five-meter spaced lines were performed to develop the "discontinued spoil area" at the above charted location. indication of the spoil area was observed. Comparison with the chart is excellent in the area. One hundred percent (100%) of the soundings agree within 1 ft.

A dangers to navigation was observed at position 2205 at the location above which was in the area of investigation. The obstruction was positioned with three lines of position (LOP) with the launch, and having an inverse distance of 1.78 The obstruction has a least depth of -8.0 ft. obstruction is described as awash at MHHW, and stacked chunks of cement reinforced with rebar (rip-rap). A Dangers to Navigation Letter, dated 23 November 1987, was sent to the Eleventh Coast Guard District, Long Beach, CA (refer to Appendix XII of this report).

### CHARTING RECOMMENDATION:

Delete "discontinued spoil area" from the above charted CONCUR position.

Chart <del>submerged</del> obstruction at the observed position.

CONCUF

CARTO-CODE 284

Already done in 12/88 P

18652 - Deleted Sp. 10p 1968 11-6 50 P

CHART: 18651 35th ed. July 5, 1986 ITEM: 168 (Shee 2 of 5)

ITEM DESCRIPTION: 10 ft shoal

SOURCE: H-9872/80

DATE	DΝ	POSITIONS	TIME	YESNO
11/07/87	311	2497-2537	2240-2306	0651
11/08/87	312	2538-2474	1805-2129	

### REFERÉNCES:

See the letter from Michael Lind, Vice President, Jerico Dredging, showing the limits of a borrow area, Appendix XIII of this report.

OIC: LT Diaz LTJG Porta

GEODETIC POSITION	Latitude N	Longitude W	Pos
Charted: Observed:	37/37/43.30 37/37/43.69	122/15/34.30 122/15/34.41	2678
(9.5 ft leas		* **** / ***** *** *** *** *** *** ***	20/0

### POSITION DETERMINED BY:

Mini-Ranger (range-range, with check)

### METHOD OF INVESTIGATION:

Forty-five-meter spaced lines were performed to develop the 10-ft sounding at the above charted location. A crossline (positions 2552-2562) was performed to check the mainscheme.

The shoal sounding was observed throughout the entire 45-m spaced development. A 10-m spaced development (positions 2563--2675) was performed to delineate the extent of the 10--ft sounding in approximately 14 to 18 ft of water. A lead line least depth of  $9.5^{7}ft$  and bottom sample (Brk Sh, M, S) were performed (position 2676) having a marginal, but acceptable inverse distance of 5.0 m. An echo sounder least depth of  $6.0^{2}ft$  (MLLW) was observed at position 2604 + 2 at the same geographic position.

One hundred percent (100%) of the soundings agree within 1 ft when compared to the chart.

On DN 313, while performing sounding operations in the area of Item 168, a dredge from Jerico Dredging Inc., Petaluma CA, was observed conducting dredging operations near the location of Item 168 as referenced above.

, copy a Hacked,

A letter (dated 01 Dec 1987) and chartlet, showing the limits of dredging, were submitted to PHP from Jerico Dredging. The area lies about 1.0 nautical mile southeast of Item 168 at about 37/37/00 N, 122/13/00 W. A phone conversation with Mr. Jerry Morris (Jerico Dredging) verified that dredging occurs in the area about two days per week and that dredging has occurred in the vicinity of Item 168 in the past.

# CHARTING RECOMMENDATION:

Survey soundings to supersede all prior surveys and charted concerdepths.

Chart 9-ft sounding at above observed position.

(see a Hacked leHer)

Chart "borrow area" outline on chart 18651, centered at Do not concur

37/37/00 N and 122/13/00 W.

Retain charted Note B

POS <u>CARTO-CODE</u> 2676 126

18652 - NC

CHART: 18651 35th ed. July 5, 1986 ITEM: 169 (Sheet 3.f5)

ITEM DESCRIPTION: 34 to 35 ft depths in 47 ft of water south of the San Mateo Hayward Bridge in the main shipping channel.

SOURCE: H-9984/81-83

DATE	DN	<u>POSITIONS</u>	TIME	YESNO
11/09/87	313	2717-2720	2149-2231	0651
11/10/87	314	2722-2723	1923-2152	0001

OIC: LTDiaz LTJG Porta

GEODETIC POSITION	Latitude N	Longitude W	POS
Charted: Search: Observed:8.4	37/35/00 48 37/35/01.50 37/35/00.99	122/15/00.00 122/14/57.80 122/15/00.82	2717 2720
(उन.र्दुt obst (46.र्दुt obst	r) 37/35/00.4 <del>9</del> r) 37/35/00.7 <del>9</del> 7	122/14/58.19 122/14/59.45	2722 * 2723

### POSITION DETERMINED BY:

Mini-Ranger (range-range, range-az with check)

# METHOD OF INVESTIGATION:

Two 100-m radius circle bottom drags were performed on DN 313 with centers at positions 2717 and 2720. The inverse distances are 2.57 and 1.29 m, respectively. Significant hangs were observed this day, however wind and sea conditions precluded dive operations. On DN 314, the searches were repeated. A significant snag (position 2722) was observed. Divers dove on the hang line to determine composition and extent of the hang. The divers acquired a least depth of 37.3 ft (MLLW) with a calibrated pneumatic gauge. This hang was positioned with the launch directly over the hang (hang line was straight up and down). The inverse was computed to be 3.9 m.

Position 2722 was described by divers as a mound of debris consisting of chunks of cement and metal scraps.

From the second circle drag (position 2720), three hangs were observed, all followed by dives. The first two hangs were insignificant. The third hang was significant (position 2723). Divers (as with position 2722) dove on the hang line to determine extent and least depth of hang. The least depth was acquired with pneumatic gauge and a detached position performed simultaneously. The least depth was 46.6 ft. The inverse distance to the check position was 0.0 m. The hang

was described by divers as a mound of cement, reinforced with rebar, protruding about 3 ft off the bottom.

Due to poor underwater visibility and strong currents it was difficult for divers to give a full description of the submerged obstructions.

Attached with this report are excerpts from the descriptive report (H-9984), preprocessing critique dated 20 July 1983 and a memo from PHP to N/MOP21 dated 11 August 1983 all concerning this item (see Appendix XIII of this report).

# CHARTING RECOMMENDATION:

(38.4 41)
Chart submerged obstruction (position 2722) with least depth concur
at the above observed position.

(46.3 ft)
Chart submerged obstruction with least depth at position 2723. Concur

Delete "Shoaling Rep 1983" from above charted position.

CONCUR

POS CARIO-CODE 2722 272 2723 272

1865 ! - Deterted M showling rep (1983) 11-3-89 A

Already done in 12/88 P

18652 - Reitse Subin cloth to Sudm Obstra 11-6-89 P

CHART: 18651 35th ed. July 5, 1986

ITEM: 170

(Sheet 3. fr)

ITEM DESCRIPTION:

Holiday on north side of the San Mateo

Hayward Bridge.

H-9984/81-83 SOURCE:

DATE\_ 11/09/87 313 POSITIONS 2676-2716

TIME 2040-2107 VESNO

OIC: LT Diaz

LTJG Porta

GEODETIC POSITION

Latitude N

Longitude W

POS

Charted:

37/35/00

122/15/06

# POSITION DETERMINED BY:

Mini-Ranger (range-range)

# METHOD OF INVESTIGATION:

Three lines, visually spaced at 50, 100, and 150 m from the north side of the San Mateo-Hayward Bridge (with the aid of a 620 Range Finder) were performed. The holiday was filled in and compared to H-9984. Comparison with the prior survey and chart are excellent. One hundred percent (100 %) of the soundings agree within 1 ft in the junction area and charted area.

# CHARTING RECOMMENDATION:

Survey depths to supersede the prior surveys and charted soundings in the area.

Revise chart with these soundings.

Concur

1/10cdy done in 12/88 P

18651 35th ed. July 5, 1986 CHART:

AWDIS 50781 ( Sheet 5 ITEM:

Submerged Dolphin

ITEM DESCRIPTION: SOURCE: H-9819/79

DATE DN 11/04/87

**POSITIONS** 2001-2023

TIME 1808-2038

**YESNO** 0651

OIC: LT Diaz

LTJG Porta

GEODETIC POSITION

Latitude N

Longitude W

POS

Charted:

37/40/17.50

122/22/11.00

Search:

37/40/17.55

122/22/11.23

2014

# POSITION DETERMINED BY:

Mini-Ranger (range-range with check)

# METHOD OF INVESTIGATION:

A 100-m radius bottom circle drag was performed with the center weight dropped at the charted position of the item (position 2014). Due to poor range-range geometry, positions 2001-2013 and 2015-2023 were rejected. These positions were the circular area swept by the drag. Position 2014 had four lines of position (LOP), a 3.3-m inverse, therefore making the center position of the drag acceptable. The 100-m drag can be performed without control once the center position has been established.

No significant hangs were observed. Sea and weather conditions were excellent.

# CHARTING RECOMMENDATION:

Delete the submerged dolphin symbol from the chart.

CONCUR

Revise the AWDIS listing as disproved.

CONCUR

I Already, done in 12/88 P 18652 - Deloted o Submodol 11-6-89 P

(Sheet 5.RS)

18651 35th ed. July 5, 1986 CHART:

ITEM: AWOIS 50782

ITEM DESCRIPTION:

Pile, summerged

SOURCE: H-9819/79

DATE DN 11/04/87 308 POSITIONS 2024-2040

OIC: LT Diaz

LTJG Porta

GEODETIC POSITION

Latitude N

Longitude W

POS

Charted:

37/40/15.Qp

122/22/23.00 122/22/23.09

2024

Search:

37/40/14.98

# POSITION DETERMINED BY:

Mini-Ranger (range-range with check)

# METHOD OF INVESTIGATION:

A 100-m radius bottom circle drag was performed with the center weight dropped at the charted position of the item (position 2024). Position 2024 had three lines of position (LOP), resulting in a marginal 7.8-m inverse. The 100-m drag was 25 m longer than required by the project instructions so the area of interest was fully covered by the drag.

No significant hangs were observed. Sea and weather conditions were excellent.

# CHARTING RECOMMENDATION:

Delete the "Pile" symbol from the chart.

CONCUR

Revise the AWOIS listing as disproved.

CONCUE

Already done in 2/88 P. 18652 - Dereted . Subm Ales 11-6-89 P

CHART: 18651 35th ed. July 5, 1986 ITEM: AWOIS 51147, 188

ITEM DESCRIPTION: Obstructions from demolition of Dumbarton bridge.

SOURCE: H-10132/84-85

DATE	DN	<u>POSITIONS</u>	TIME	YESNO
11/11/87	315	2724-2742	1826-2104	0651
11/12/87,	316	2745-2749	2112-2338	0651-0654
11/16/87	320	2752-2764	1901-2326	0651

OIC: LT Diaz LTJG Porta

GEODETIC POSITION	Latitude N	Longitude W	POS
Charted:	37/30/16.70	122/07/07.32	
Search:	37/30/15.74	122/07/06.83	2745
Oh	37/30/20.80	122/07/01.18	2753
Observed:	1		•
(old bridge limit)	37/30/11.5æ	122/07/15.79	27321
(old bridge limit)	37/30/24.37	122/06/56.57	2737
*(bridge fender)	37/30/19.653	122/07/03.5+2	2733
*(bridge fender)	37/30/21.1±0	122/07/05.02 <sup>3</sup>	2734
*(bridge fender)	37/30/21.8±°	122/07/00.27	2735
*(bridge fender)	37/30/2 <u>3</u> .29 <sup>8</sup>	122/07/01.78	2736
(28.2ft obstr)	37/30/14:34	122/07/07:07	2752
( <del>29.4</del> ft obstr)	37/30/22 <b>.</b> 8 <del>5</del> 2	122/06/59.9+4	2755

\*These also position a "red" fender light at the north and south ends of the east and west fenders of the new Dumbarton Bridge.

# POSITION DETERMINED BY:

Mini-Ranger (range-range, range-azimuth) and sextant-sextant checks

# METHOD OF INVESTIGATION:

AWDIS Item 51147 required much planning and time consuming methods to conduct a full investigation of the common area to determine, verify, and prove existence of any bottom debris.

On DN 315, PHP performed three controlled reconnaissance sounding lines from the east bridge extension to the west bridge extension (now both fishing piers) which are the only visible remains of the old Dumbarton Bridge. The reconnaissance lines (positions 2724-2731) showed evidence of a very irregular bottom. The new Dumbarton Highway Bridge was built just north of the location of the old bridge. (See photographs in Appendix XIII). The west and east extensions of the old bridge were positioned (positions 2732 and 2737)

using range-azimuth with a visual check. Positions 2732 and 2737 have inverse checks of 3.8 and 1.0 m, respectively.

The east and west fenders and lights (located at the north and south ends of the fenders) of the new Dumbarton Highway Bridge were positioned (positions 2733-2736) with a range-azimuth and visual check. All inverse distances were less than 5 m, therefore acceptable for a 1:10000-scale survey.

The AWOIS survey requirement called for a 75-m minimum radius wire drag, for a 26.5-ft obstruction at 37/30/16.70 N, 122/07/07.32 W. Since PHP had limitations of resources and personnel, the hydrographers decided that a two-boat wire bottom drag operation would not be as advantageous, in this location (close to the bridge tiers), as a 100-m radius circle bottom drag which requires one boat. The center of the drag was at position 2745, the GP is listed above.

No significant hangs were observed at this location.

The survey requirements for AWOIS 51147 required a wire drag be performed in the area common to the position of the old Dumbarton bridge that was demolished and to ensure all debris had been removed.

A bottom wire drag, covering approximately a 120-m swath (see Figure 2, Appendix XIII), was performed on DN 316 with the Launch 1101 (EDP 0654) and the Boston Whaler (EDP 0654). operation was difficult and cumbersome with the limited resources and personnel available. The drag went from the east fender of the old bridge to about 100 m beyond the west fender of the new bridge (positions 2745-2749). On the first pass the drag hung hard on the bottom. Divers went down the hang line in the usual treacherous, strong currents and 0 ft visibility water to encounter hard, jagged and sharp rubble protruding about 4 ft off the bottom. The divers had to return to the surface as one of the diver's dry suit inflater valve malfunctioned. This concluded dive operations for this day. No least depth was measured due to the malfunction. wire was hung and wrapped so hard that it had to be cut loose. Most of the drag apparatus was lost on this day. A marker buoy and line were attached to wire that was hung on the obstruction.

On DN 320, Launch 1101 returned to the location of the last hang from DN 316, position 2750 (rejected), to discover the marker buoy had disappeared. A 30-m radius bottom circle drag (same basic configuration as 100-m radius circle drag), with center position at 2751(rejected), was performed using the same Mini Ranger rates from position 2750. Operating in strong currents, a hang was observed at position 2752. This was the same hang encountered on DN 316, position 2750. Divers went down the hang line to determine extent and composition of hang. A least depth, using a calibrated

pneumatic gauge and a detached position were observed. The least depth of the obstruction was computed to be 28.2 ft (MLLW). The obstruction was described as two wooden pilings and a mound of sharp, jagged metal debris, protruding about 3-4 ft off the bottom.

A 100-m radius bottom circle drag (center at position 2753) was performed to drag the area of the main ship channel common to the area of the old Dumbarton bridge, just slightly south of the east and west bridge fenders of the new Dumbarton bridge. No significant hangs were observed.

The entire area of the ship channel common to the old bridge was bottom dragged. No debris exists within the main ship channel.

A hang was observed east of the main ship channel at position 2755 and common to area of the old bridge. Divers went down the hang line, to determine extent and composition of the hang. A least depth and detached position were observed. The least depth was acquired with a pneumatic gauge and computed to be 27.1 ft (MLLW). The launch positioned itself over the hang to acquire a range-range and range-azimuth check. The inverse distance is 1.0 m. The obstruction was described as a group of old pilings and dolphins (bridge ruins) protruding about 6 or 7 ft above the bottom. The drag line was wrapped so badly around the obstruction, it had to be cut. Much of the drag line was lost.

On 30 NOV 1987, Mr. Wayne Till (U.S. Coast Guard bridge section) was contacted by telephone (415-437-3514) to inform his office of our findings. See letter from U.S. Coast Guard to CALTRANS dated 05 February 1988, in Appendix XIII.

A Dangers to Navigation Letter, dated 16 Dec 1987, was submitted to the 11th USCG concerning these findings near the Dumbarton bridge. A copy of this letter is attached (Appendix XII).

### CHARTING RECOMMENDATION:

Chart submerged obstructions and least depths described by comor positions 2752 and 2755.

Chart the bridge fenders and lights for the new Dumbarton concurring Highway Bridge. See Section N Sc Sc.

Chart the submerged ruins area between positions 2732 and Concor 2737, except for the area between the main ship channel, common to the old Dumbarton Bridge (refer to the Dangers to Navigation Letter dated 16 Dec 1987, Applica XII).

The circle drag performed at position 2745, although no significant hangs were observed, the area of the drag area

lies within the submerged ruins area mentioned above. Chart concurthis area the same as above.

Chart the fishing piers extending 12 m and 140 degrees T from concorthe east and west extensions of the old Dumbarton Bridge (see positions 2732 and 2737).

<u> Pos</u>	CARTO-CODE
2732	057
2733-2736	200, 425
2737	057
2752	272
2755	272

Already done in 12/68. @

18652 - NC

# M. ADEQUACY OF SURVEY.

These investigations are complete and adequate to supersede concvoall prior charted and item information.

See Section A of this report, for a discussion of the items which were not completed.

N. AIDS TO NAVIGATION. See Eval Rpt Cat 7.d.

Non Floating Aids to Navigation

There were no floating aids to navigation with the areas of concurthese investigations.

The following fixed aids to navigation were used for calibrations and were positioned (verified) to Third Order, Class I accuracy (See Horizontal Control Report, South San Francisco Bay, CA., OPR-L123-PHP-87). The only exceptions were the Dumbarton Bridge fender lights which were established in early 1986 and positioned using hydrographic methods. Comparisons of the field positions of the fixed aids to navigation were performed to the U. S. Coast Guard Light List, Yolume YI. 1988, and the September, 1986 DIFFILE Listing for fixed aids to navigation (most recent Dipfile Listing for Chart 18651 available to PHP).

The names for South San Francisco Yacht Harbor Light 1 and 2 were changed to Oyster Point Marina Light 1 and 2, respectfully to reflect the names used by local mariners and by the Light List (numbers 5100 and 5105). These changes will be reflected on the Horizontal Control Report, which will shortly follow this report.

OYSTER	POINT	MARINA	LIGHT	1	(formerly	C	SE	VCUT	upp			
				*	vio: merty	_	-1C	YUHI	HBR	LT	1)	

Field position	37/39/50.908	<u>Long_W</u> 122/22/05.098	INV (m)
Light List #5100		122/22.1	97.87
DIPFILE		122/22/05.098	0.015

# DYSTER POINT MARINA LIGHT 2 (formerly S SF YCHT HBR LT 2)

Field position Light List #5105	37/39/52.110	122/22/05.186	INV (m)
DIPFILE		122/22/05.186	0.015

# COYOTE POINT YACHT HARB LT 1

Field position	<u>Lat_N</u> 37/35/36.724	<u>Long W</u> 122/18/41.294	INV (m)
Light List #5140	37/35.6	122/18.7	28.263
DIPFILE	37/35/36.726	122/18/41.302	0.200

SAN	FRANCISCO BAY S CH L			
	Field position *Light List #5270 DIPFILE	37/30.8	Long W 122/08/01.872 122/08.0	INV (m) 70.11
DUME	BARTON BRIDGE W FENDE Pos 2733	R S LT (RED)		
	TO TO THE OWN A	<u>Lat N</u> 37/30/19.65 none none	<u>Long W</u> 122/07/03.51	INV (m) - -
DUME	BARTON BRIDGE W FENDE Pos 2734	• ,		
	Field position Light List DIPFILE	<u>Lat_N</u> 37/30/21.11 none none	<u>Long_W</u> 122/07/05.02	INV (m)
DUMB	ARTON BRIDGE E FENDE Pos 2735			•
	Field position Light List DIPFILE	<u>Lat_N</u> 37/30/21.81 none none	Long_W 122/07/00.27	INV_(m) - -
DUMB	ARTON BRIDGE E FENDE Pos 2736			
	Field position Light List DIPFILE	<u>Lat N</u> 37/30/23.29 none none	<u>Long W</u> 122/07/01.78	<u>INV (m)</u> -
*The	characteristic and	geographic posit	tion for "San Fr	rancisco

\*The characteristic and geographic position for "San Francisco S Ch LT 14" is listed as "Redwood Creek LT 14" (Light List #5270). Refer to letter to Eleventh Coast Guard District dated 03 February 1988, Appendix XIII.

NOAA Form 76-40 has been attached.in Appendix X.

# O. STATISTICS.

Vessel: Launch 1101, EDP 0651 Number of Positions: . 764 N. miles of Sounding Lines: 54.0 Square nm of Hydrography: 2.0 Detached positions: 28 Number of tide gages: 2 (POG gages: 2. See Field Tide Note.) Days of production: 15

### P. MISCELLANEOUS.

There were no anomalous currents, tides, or submarine features in the areas of investigation.

Two bottom samples were acquired, but not sent to the Smithsonian Institute, because it was not required by the project instructions. Bottom samples (pos 2496, 2676) were taken at the hydrographers discretion to determine the bottom configuration of the feature being investigated.

# Q. RECOMMENDATIONS.

See Eval Rph Seet 9

Refer to sections L, M, and N for individual recommendations

# R. AUTOMATED DATA PROCESSING.

# DEC PDP 8/e Computer

MTEN

		**************************************	
	Number	Name	<u>Yersion Date</u>
	RK201 RK221 RK226 RK300 RK330 RK360 RK362	Grid, Signal, and Lattice Plot Range-Range Non-Real Time Plot Range-Azimuth Non-Real Time Plot Utility Computations Reformat and Data Check Electronic Corrector Abstract Reformat and Data Check and Elinore-Line Oriented Generator	4/18/75 7/25/86 7/25/86 10/21/80 5/04/76 2/02/76 8/20/84
	AM500 RK561	Predicted Tide Generator H/R Geodetic Calibration	11/10/72 12/01/82
Hewlett Packard 9815A Calculator.			
	Number .	Name	Yersion Date
	811101	Geodetic Package	Feb. 1985
	Hewlett P	ackard 97 Calculator.	
	Number	Name	<u> Version Date</u>
		Geodetic Inverse	
	IBM PC .		
	Number	Name	<u>Version</u> Date

Micro - Terminal Entry Command

<u>Version Date</u>

Nov. 1984

# S. REFERRAL IO REPORTS.

Other reports covering this survey area are:

- 1) <u>Horizontal Control Report</u>, <u>South San Francisco Bay</u>, <u>CA.</u>, <u>OPR-L123-PHP-87</u> (the report will be submitted at a later date).
- 2) Horizontal Control Report, <u>San Francisco Bay and San Pablo Bay, CA., OPR-L123-PHP-87</u> dated March, 1987 to October, 1987 (submitted to PMC for verification)

Submitted by.

Federico R. Diaz, SDA

CHIEF

PACIFIC HYDROGRAPHIC PARTY NATIONAL OCEAN SERVICE (NOS)

#### FIELD TIDE NOTE

OPR-L123-PHP-87
FIELD EXAMINATION
San Francisco Bay, California (Items)
PHP-10-4-87
Chart 18651

### Reductions

Soundings on the field sheet were reduced on the basis of predicted tides for San Francisco, (Golden Gate, Presidio) Fort Point, Calif., station number 941-4290. Tide correctors were generated at 0.2 ft intervals using the PDP-8e computer system and program AM 500 "Predicted Tide Generator".

#### Stations

Three permanent tide stations bracket the survey area. These three stations are operated by NOAA, Pacific Operations Group, N/OMA 1214. The gage at San Francisco, Fort Point 941-4290 is to the northwest of the survey area, Alameda (Alameda NAS) 941-4750 is to the north, and San Mateo Fishing Pier 941-4458 is to the west northwest. San Mateo Fishing Pier was not required by the project instructions, but may prove helpful in real tide reductions. Frequent checks with POG confirmed that there were no significant breaks in the data from these stations. There were no breaks at Alameda (941-4750). Fort Point (941-4290) was down from 29 May to 3 June and again from 14 July to 16 July. Since there are backup gages at this site there should be no problem with data reduction. These sites were leveled by Pacific Operations Group in October. There were no other problems.

No tide stations were installed or operated by PHP during these item investigations.

## <u>Tide Zone Correctors</u>

Predicted tides from the San Francisco, Fort Point tide gage were adjusted by the application of correctors supplied by NOAA, Office of Oceanography and Marine Assistance, Sea and Lake Levels Branch, Rockville, Md (N/OMA 121). These correctors accompany project instructions OPR-L123-PHP-87, dated 10 Feb. 1987.

The correctors used for this Field Exam Survey are as follows:

## ITEMS No. 160, 162, 166, 167 AWIOS 50781, and 50782

- + 0 hr. 41 min. High Water
- + 1 hr. 00 min. Low Water
- X 1.29 Height Ratio

### ITEM No. 168

- + 0 hr. 48 min. High Water
- + 1 hr. 16 min. Low Water
- X 1.36 Height Ratio

### ITEM No. 169, 170

- + 0 hr. 43 min. High Water
- + 1 hr. 13 min. Low Water
- X 1.41 Height Ratio

#### AWOIS 51147

- + 1 hr. 00 min. High Water
- + 1 hr. 40 min. Low Water
- X 1.61 Height Ratio

No survey data was acquired without the required tide support. Pacific Standard Time (120 W.) was used at the permanent stations operated by POG N/OMA 1214.

Submitted by

Kul 10

Bruce H. Lund Eng. Tech. Approved by

Lt. Federico Diaz,NOAA Chief, PHP (N/MOP223)

#### SIGNAL TAPE LISTING

```
613 0 37 46 30047 122 14 31590 250 0003 000000 SOHIO
614 Ø 37 54 Ø89 78 122 21 35 718 25Ø ØØØ6 ØØØØØØ POINT PETRERO RCH RNG E LT
616 C 37 47 02222 122 14 50935 250 0002 200000 VET 2
617 C 37 47 C9168 122 15 26443 250 0003 202000 9TH AVE PM 1
618 6 27 49 14966 122 19 44838 258 8883 66888 MOLE 1947
610 2 27 48 58558 132 21 38637 139 0824 38868 ARMY 2 1947
620 0 37 43 36125 122 21 28488 250 0039 000000 BUILDING 253 1948
621 C 37 46 C2578 122 18 25655 25C 0007 000000 ALAMEDA NAS E BREAKWATER 6 LT
600 2 37 46 24620 122 17 56041 250 0010 000000 ALAMEDA NAS CHANNEL RNG F LT
      - 27 46 23264 122 17 31750 139 0023 000000 ALAMEDA NAS CHANNEL RNG R-LT
    2 37 44 36414 122 15 34434 258 8883 88828 BAY FARM NW
505 ( 37 44 36876 100 15 33410 250 0003 200000 BAY FARM NW RM 1
626 2 37 45 46418 122 15 08227 139 0029 000000 HOSPITAL 1947
627 0 37 45 46511 122 15 08308 139 0000 000000 HOSPITAL 1947 RM 3
678 8 37 44 58869 122 14 07210 250 0013 000000 SAN LEANDRO CHAN
629 0 37 45 36186 122 13 19302 250 0003 000000 UNIFLEX
630 C -37 45 56541 132 12 00435 139 0000 000000 OAKLAND SAFEWAY TOWER STEEPLE
631 0 37 44 56214 122 13 19641 243 0000 000000 SAN LEANDRO BAY AIRPORT DBCN 3
632 C 37 44 55519 122 13 20656 243 0000 000000 SAN LEANDRO BAY AIRPORT DBCN 4
635 @ 37 43 58948 122 12 28227 243 8888 88888 OAK AP CHAN HYDRO SIGNAL
637 8 37 43 33562 122 13 21819 139 8888 8888 900 VORTAG OAKLAND OAK
638 0 37 42 55060 122 23 33741 139 0128 000000 BAY PARK 1932
639 2 37 39 12095 122 23 01817 250 0055 000000 POINT SAN BRUNO 1925
640 0 37 40 27542 122 23 33262 250 0148 000000 SIERRA POINT 1851
641 Ø 37 39 50908 122 22 05098 139 0000 000000 OYSTER POINT MARINA LT 1
642 0 37 39 52110 122 22 05186 139 0000 000000 OYSTER POINT MARINA LT 2
643 Ø 37 35 36724 122 18 41294 139 ØØØØ @@@@@@COYOTE POINT YACHT HARB LT 1
644 0 37 35 28848 122 19 06017 250 0013 000000 POINT SAN MATEO 1925
645 @ 37 30 49716 122 08 01872 139 0000 000000 SAN FRANCISCO BAY S CH LT 14
646 Ø 37 30 Ø2107 122 Ø6 20944 250 Ø004 Ø0000@ HETCHY 1983
647 @ 37 33 14065 122 05 36907 250 0089 000000 RED HILL TOP 1958
```

LIGHT OPR-L123-PHP-8; The following objects
OPR PROJECT NO. NOAA FORM 76-40 (8-74) Replaces C&GS Form 567. CHARTING NAME TO BE DELETED TO BE REVISED = = TO BE CHARTED = "FL G 4sec 12ft," COYOTE POINT YACHT HARBOR LICHT 1 South SAN FRANCISCO YACHT HARBOR LIGHT.

1) "FL G 4s 17ft" (name change on hy SOUTH SAN FRANÇISCO YACHT HARBOR LICHT OYSTER POINT MARINA LIGHT 2 (Formally OYSTER POINT MARINA LIGHT 1 (Formally Show triangulation station names, where applicable, in parentheses, DESCRIPTION
(Record resean for deletion of landmark or aid to navigation. FRANCISCO BAY SOUTH CHANNEL LIGHT "FL R 48" (name change only HAVE HAVE NOT been inspected from seaward to determine their value as landmarks. PACIFIC HYDROGRAPHIC JOB NUMBER REPORTING UNIT "FL R 4s 15ft 4m" U.S. DEPARTMENT OF COMMERCE NONFLOATING AIDS OR LANDMARKS FOR CHARTS E SURVEY NUMBER CHART 18651 CALIFORNIA 37 39 37 39 37 30 3 NORTH AMERICAN DATUM 1927 MUTAG ä LATITUDE 49.716 36,724 D.M. Meters 50.908 SAN FRANCISCO BAY (SOUTHERN PORTION) POSITION 122 08 122 122 22 22 22 LONGITUDE 18 01.872 25.186 05.098D.P. Meters 294 METHOD AND DATE OF LOCATION (See Instructions on reverse side) OFFICE 01/25/88 DATE COAST PILOT BRANCH (See reverse for responsible personnel) DHOTO FIELD PARTY
COMPILATION ACTIVITY
FINAL REVIEWER X HYDROGRAPHIC PARTY F-2-6-L FINAL REVIEWER = = FIELD ORIGINATING ACTIVITY AFFECTED 18651 CHARTS = = =

5 N

etric methods.	. ₹.	ed by field obser- ground survey methods.	*FIELD POSITIONS are determined by field obser- vations based entirely upon ground survey meth
C FIELD POSITIONS are dependent	**PHOTOGRAMMETRIC FIELD		8-12-75
	EXAMPLE: V-VIs. 8-12-75	require entry of method of of field work.	sitions*
POSITION VERIFIED VISUALLY ON PHOTOGRAPH Enter 'V-Vis.' and date.	III. POSITION VERIFIED VISUAL Enter 'V-Vis.' and date.	Planetable Sextant	3 - Intersection 7 - F 4 - Resection 8 - S
2000.	8-12-75	Field Identified Theodolite	ation 5 -
ION RECOVERED ald which is also a tri- is recovered, enter 'Triang. recovery.	ATION STATI andmark or on station th date of	NED OR VERIFIED data by symbols as follows: P - Photogrammetric Vis - Visually	<pre>I. NEW POSITION DETERMINED OR VERIFIED Enter the applicable data by symbols F - Field P - Photogrammet L - Located Vis - Visually V - Verified</pre>
2982	74L(C)2982		FIELD
ed to locate or identify the object.  P-8-V 8-19-75		the \bject.	<pre>identify and locate the  EXAMPLE: 75E(C)6042 8-12-75</pre>
method of location or verification, field work and number of the photo-	entry of method c	(including month, tograph used to	
		ATED OBJECTS	OFFICE IDENTIFIED AND LOCATED OBJECTS
	OR ENTRIES UNDER 'METHOD AND DATE OF LOCATION (Consult Photogrammetric Instructions No. 64,	INSTRUCTIONS FOR ENTRIES UNDER 'METHOD AND DATE OF LOCATION' (Consult Photogrammetric Instructions No. 64,	
REPRESENTATIVE			ACTIVITIES
D D M V IM WE D			FORMS ORIGINATED BY QUALITY CONTROL AND REVIEW GROUP AND FINAL REVIEW
OFFICE ACTIVITY REPRESENTATIVE			
FIELD ACTIVITY REPRESENTATIVE	VD (verified)	ENG TECH BRUCE H. LUND	F-0511 IONS DETERMINED AND/OR VERIFIED
OTHER (Specify)			
GEODETIC PARTY	LTJG Thomas K. Porta	LI rederico K. Diaz/LTJG	
HYDROGRAPHIC PARTY		: -	OBJECTS INSPECTED FROM SEAWARD
ORIGINATOR	NASM	7	TITE OF ACTION
	ייי ביייט לייייר בייי		TYPE OF ACTION
	RESPONSIBLE PERSONNEL	RESPONSIBL	

NOAA FORM 76-40 (8-74)

SUPERSEDES NOAA FORM 78-40 (2-71) WHICH IS OBSOLETE, AND EXISTING STOCK SHOULD BE DESTROYED UPON RECEIPT OF REVISION.

会 U.S.GPO:1975-0-865-080/1155

The following objects
OPR PROJECT NO. X TO BE CHARTED Replaces C&GS Form 567. NOAA FORM 76-40 (8-74) LIGHT TO BE DELETED CHARTING OPR-L123-PHP-8 TO BE REVISED = = = ZAME (Record reason for deletion of landmark or aid to navigation. Show triangulation station names, where applicable, in perentheses, DUMBARTON BRIDGE W. FENDER S. LT (RED) = = = HAVE HA REPORTING UNIT
(Field Perry, Ship or Office)
PACIFIC HYDROGRAPHIC PART = = = HAVE NOT DESCRIPTION NONFLOATING AIDS OR LANDMARKS FOR CHARTS = H . = Ξ = = been inspected from seaward to determine their value as landmarks.

SURVEY NUMBER DATUM z S Z = = = CALIFORNIA STATE = = = 37 37 37 37 NORTH AMERICAN DATUM 1927 0 30 30 30 30 LATITUDE U.S. DEPARTMENT OF COMMERCE 23.290 19.650 D.M. Meters 1.810 LOCALITY SAN FRANCISCO BAY (SOUTHERN PORTION) POSITION 122 07 122 122 07 122 • LONGITUDE 07 07 01.780 00.270 D.P. Meters 05.020 03.510 METHOD AND DATE OF LOCATION (See instructions on reverse side) OFF ICE 1 DATE 01/29/88 QUALITY CONTROL & REVIEW GRP. MHYDROGRAPHIC PARTY
GEODETIC PARTY
PHOTO FIELD PARTY (See reverse for responsible personnel) COMPILATION ACTIVITY TINAL REVIEWER F-3-8-L ORIGINATING ACTIVITY FIELD Ξ = = AFFECTED 18651 CHARTS Έ = =

\*\*\ \\_\_\_\_

3 - Intersection 7 - Planetable 4 - Resection 8 - Sextant A. Field positions* require entry of method of location and date of field work.  EXAMPLE: F-2-6-L EXAMPLE: F-2-75  **PHOTOGRAMMETRIC FIELD POSITIONS are dependent entirely upon ground survey methods.  *FIELD POSITIONS are determined by field obser-by photogrammetric methods.	EW POSITION DETERMINED OR VERIFIED  nter the applicable data by symbols as follows:  - Field  - Photogrammetric  - Located  - Verified  - Triangulation  - Traverse  - Traverse  - Triangulation  - Traverse		INSTRUCTIONS FOR ENTRIES UNDER 'METHOD AND DATE OF LOCATION' (Consult Photogrammetric Instructions No. 64.	FORMS ORIGINATED BY QUALITY CONTROL  AND REVIEW GROUP AND FINAL REVIEW  QUALITY CON  ACTIVITIES  REPRESENTA	LT FEDERICO R. DIAZ	OBJECTS INSPECTED FROM SEAWARD  PACIFIC HYDROGRAPHIC PARTY  GEODETIC PACIFIC PARTY  OTHER (Species of the content of the conte	TYPE OF ACTION
IFIED VISUALLY ON PHOTOGRAPH .' and date. Vis. 12-75 12-75 FIELD POSITIONS are dependent part, upon control established ric methods.	N RECOVERED id which is also a tri- s recovered, enter 'Triang. ecovery. c.	mmetric field positions** require method of location or verification, field work and number of the photo- ed to locate or identify the object. P-8-V 8-12-75 74L(C)2982		REVIEWER  QUALITY CONTROL AND REVIEW GROUP  REPRESENTATIVE	FIELD ACTIVITY REPRESENTATIVE	XX PHOTO FIELD PARTY  HYDROGRAPHIC PARTY  GEODETIC PARTY  OTHER (Specify)	ORIGINATOR

NOAA FORM 78-40 (8-74)

SUPERSEDES NOAA FORM 74-40 (2-71) WHICH IS OBSOLETE, AND EXISTING STOCK SHOULD BE DESTROYED UPON RECEIPT OF REVISION.

分 U.S.GPO:1975-0-865-080/1155



# U.S. DEPARTMENT OF COMMERCE National Oceanic and Atmospheric Administration NATIONAL OCEAN SERVICE

Pacific Hydrographic Party 614 A East Fifth St. Benicia, CA 94510

23 November 1987

Cummander (oan)
11TH Coast Guard District
Fuilding 51, Government Island
Alameda, CA 94501

#### Dear Sir:

The following features were observed by the Pacific Hydrographic Party, NOS, NOAA, during a field examination of South San Francisco Bay. The features were discovered on O6 November 1987 during survey operations near Dyster Point Enterance Marina. This information, which is field data, is subject to verification, and will be used to update future editions of nautical chart 18651. It is, however, considered important enough to warrant immediate publication.

#### **OBSTRUCTIONS**

The following uncharted obstructions and hazards were found during the item investigations. The surveyed depths have been corrected to the chart datum, which is mean lower low water (MLLW), by applying predicted tides. The surveyed depths are field data and are subject to change. The geodetic positions are based on the North American Datum 1927 (NAD 1927).

Description Latitude Longitude (NAD 1927)	Least Depth (MLLW)	
Submerged 37/39/56.90 N 122/22/47.20 Obstruction	•	/
Submerged 37/40/06.71 N 122/22/55.46 Obstruction	W -6.6 ft/	<i>L.</i>
Submerged 37/40/06.40 N 122/22/54.42 Obstruction	W -8.6 ft.	V

All three obstructions are awash or submerged at MHHW.

for further information concerning the above mentioned obstructions contact the Chief of Party, Pacific



Hydrographic Party-NOAA, 614 A East 5th St. Benicia, 94510. The Chief of Party may be reached locally in Benicia at the following phone number: 707-746-8189.

Respectfully

Federico R. Díaz

LT NOAA

Chief of Party

cc: Chart Information Section, N/CG222 Nautical Charts Branch, N/MOP21 1/69' AND 188



### U.S. DEPICOMICO OF COMMERCE National Oceanic and Atmospheric Administratio NATIONAL OCEAN SERVICE

PACIFIC HYDROGRAPHIC PARTY 614-A East 5TH Street Denicia, CA 94510

16 December 1987

Commander (oan)
Eleventh Coast Guard District
Union Bank Building
Long Beach, CA 90822

Dear Sir:

The following features were observed by the Pacific Hydrographic Party, NOAA, National Ocean Service, during field examinations of South San Francisco Bay. The features were discovered on November 09, 11, and 16, while performing survey and dive operations near the San Mateo-Hayward Bridge and the Dumbarton Highway Bridge. This information is field data, which is subject to verification, will be used to an update future editions of Chart #18651. It is, however, considered important enough to warrant immediate publication.

The following uncharted obstructions surveyed depths have been corrected to the chart datum, which is Mean Lower Low Waters (MLLW) by applying predicted tides. The geographic positions are based on the North American Datum 1927 (NAD27).

While performing operations in the vicinity of the San Mateo-Hayward Bridge and the main shipping channel, two submerged obstructions with least depths of 37.3 ft. and 46.6 ft. were observed at the following geographic positions:

Lat. 037/35/00.5N and Lat. 037/35/00.8N Lon. 122/14/59.4W

See attached chartlet #1 of Chart 18651.

Operations were performed on the 11 and 16 November 1987 in the Vicinity of the "new" Dumbarton Bridge, common to the area of the "old" Dumbarton Bridge which was recently blown up. Bottom drag and dive operations proved that there is no bottom debris in the main shipping channel common to the area where the "old" Dumbarton Bridge used to exist, therefore, no obstructions exist in the main channel.

The same types of operations proved that several obstructions exist east and west of the main shipping



channel, within the area common to where the "old" Dumbarton Bridge existed.

The attached chartlet #2 of Chart 18651 shows the area of the main shipping channel and the "old" bridge clear of obstructions. East and west of the ship channel, common to the area of the "old" Dumbarton Bridge, should be charted as submerged ruins to the following geographic positions of the existing east and west bridge fenders of the "old" bridge:

West Fender Lat. 037/30/11.5N Lon. 122/07/15.8W

East fender Lat. 037/30/24.3N° Lon. 122/06/56.6W

For further information concerning the above mentioned obstructions, contact the Chief of Party, Pacific Hydrographic Party-NOAA, 614-A East 5TH Street, Benicia, CA 94510. The Chief of Party may be reached at the following phone number: 707-746-8189.


Respectfully.


Federico R. Diaz

Chief, PHP

CC: Chart Information Section, N/CG222 Nautical Chart Branch. N/MOP21

THE PARTY WHEN THE PROPERTY OF





## AWOIS 51147 (ITEM 188)

NEW DUMBARTH BRIDGE EAST-WEST FENDERS

DUMBARTON BRIDGE (EAST SIDE)
Looking to western bridge fender of "old" bridge

ALEW DUMBACTE BRIDGE


DUMBARTON BRIDGE (WEST SIDE)
Looking to eastern brige fender of
"old" bridge

11/11/87

11/11/87



DUMBARTON BRIDGE (WEST SIDE)



DUMBARTON BRIDGE (EAST SIDE)

11/11/87



#### U.S. DEPARTMENT OF COMMERCE National Oceanic and Atmospheric Administration NATIONAL OCEAN SERVICE

PACIFIC HYDROGRAPHIC PARTY 614-A East 5TH St. Benicia, CA 94510

03 February 1987 N/MOP223:frd

COMMANDER (oan) Eleventh Coast Guard District Union Bank Building Long Beach, CA 90822

Dear Sir:

An error was recently discovered by the FACIFIC HYDROGRAPHIC PARTY (FHP) in the U.S. Coast Guard Light List Volume VI. 1988, Pacific Coast And Facific Islands. The characteristics and geographic position for "Redwood Creek LT 14" (Light List number 5270) is actually "San Francisco South Channel LT 14", which is not listed in the Light List. Attached with this memo are copies of pages 57 - 58 of the Light List. PHP considered this important enough to warrant immediate notification and publication. Your cooperation in this matter is appreciated.

Respectfully

Federico R. Díaz

Chief, PHP

cc: Chart Information Section, N/CG222 Nautical Chart Branch, N/MOP21



No	Name and location	(3) Position	(4) Characteristic	(5) Heigh	t Rar	(7) Structure	e (8) Remarks
			CALIFORN	IA - Ele	venth	District	
	SAN FRANCISCO BAY .	N/W SOUTHERN PART	[ (Chart 1865])				
	South Channel						
5155	Son Mateo-Hayward Bri Fog Signal	dge					HORNS: 2 blasts ev 30s (3s bl-3s si-3s bl-21s si)
5160	- Buoy 10	37 35.0 122 15.1				Red nun.	Private aid.
5165	- Buoy II	37 35.0 122 14.9				Green can.	
5170	- TOWER LIGHT	37 34.9 122 15.0	FI W 2.5s	12.		Transmission tower.	Private aid.
5175	- LIGHT 12		FI R 45	15	4	TR on pile.	Higher intensity beam down channel toward San Mateo-Hayward Bridge.
	Redwood Creek						Ra ref.
5180	- ENTRANCE LIGHT 2	37 33.2 122 11.8	Ħ R 4*	15	4	TR on pile.	HORN: 1 blast ev 10* (1* bf). Operates continuously from Oct. 1 to Apr. 1.
							Higher intensity beam upstream
5185	- ENTRANCE LIGHT 3	,	1 0 42	15	3	SG on pile.	Rairef.
190	- ENTRANCE LIGHT 4	F	1 R 44	15	4	TR on pile.	Ra ref.
195	- LIGHT 5	37 32.4 FF 122 11.5	l G 4º	15	3	SG on pile.	Ra ref.
200	- LIGHT 6		R 49	1.0			746 746.
205	- LIGHT 8		24	15	4	TR on pile.	
210	- LIGHT 7		<b>G</b> 2.5•	15	3	TR on pile,	
215	- LIGHT 10		R 44	15	3	SG on pile.	Ra ref.
20	- LIGHT 9	n et		15	3	TR on pile.	
25	- Daybeacon 11	n	G 4s		3	SG on pile.	Ra ret,
30	- LIGHT 12		<b>R</b> 6s			SG on pile.	
	- LIGHT 14		R 0-	15	4	TR on pile.	
	- LIGHT 13			15	3	TR on pile.	Ra ref.
	- LIGHT 15		G 2.5*	15	3	SG on pile.	Rairef.
	- LIGHT 16		- 4	15	5	SG on dolphin.	
	- LIGHT 18			15	4	TR on pile.	Ra ref.
		37 30.8 FI I 122 12.7	<b>t</b> 4s	15	4	TR on pile.	Ra ref.
	· LIGHT 20	FI I	t 4s	15	3	TR on column.	De sut
	Daybeacon 21				-	SG on pile.	Ra ref.
0 -	LIGHT 14	37 30.8 FI R 122 08.0	45	15	4	TR on pile.	Higher intensity beam down - channel,
5 <b>D</b> •	umbarton Highway Bridge Fog Signal	37 30.4 122 07.0				٠.	Ra ref.  HORN: 1 blast ev 20s (2s bl).  Private aid.

	(1) No.	(2) Name and location	(3) Position	(4) Characteristic	(5) Height	(6) Range	(7) Structure	(8) Remarks
				CALIFORNIA	- Elev	onth Dist	rict	
		SAN FRANCISCO BAY - SOL	n/w JTHERN PAR	(Chart 18651)				
		Redwood Creek						
	5280	Dumbarton Railroad Bridge Fog Signal	37 29.9 122 06.5					BELL: 1 stroke ev 20s Private aid.
		Mayfield Slough						
	5285	- Entrance Daybeacon 2	37 29.5 122 06.9				Pile	Private aid.
	5290	- Entrance Daybeacon 4					Pile.	Private aid.
	5295	- Entrance Daybeacon 6					Pile.	Private aid.
	5300	- ENTRANCE LIGHT 8	37 28.1 122 05.8	fl W 45	25		Platform on piles.	Private aid.
111414	<b>→</b> >	South Channel						
	5305	- LIGHT 16		FI R 4s	15	3	TR on pile.	Rairet.
	5310	- LIGHT 17		FI G 45	15	3	SG on pile.	Ra ref.
	5315	- LIGHT 18		FI R 45	15	3	TR on pile.	Ra ref.
	5320	- Daybeacon 20					TR on pile	3
	1	Guadalupe Slough					•	1
	τ,	Buoys are located to best man	k shifting ch	annel.				·
	5325	- Buoy 1					Green can.	
	5330	- Buoy 2					Red nun.	
	5335	- Buoy 3					Green can.	
	5340	- Buoy 4					Red nun.	
	5345	- Buoy 6		•			Red nun.	
		SAN FRANCISCO ENTRANCE	(Chart 1864)	9)				
		San Francisco Bay		•				
	5350	- North Channel Lighted Buoy 2	37 50.0 122 23.7	FI R 65		4	Red.	
	5355	- North Channel Buoy 3	37 51.0 122 25.0				Green can.	
		Emeryville Marina						
	5360	- LIGHT 1	37 50.6 122 19.3	FI G 25	14		SG on pile.	Private aid.
	5365	- LIGHT 2		FI R 25	14		TR on pile.	Private aid.
	5370	- LIGHT 3	37 50.6 122 18.9	FI G 4s	14		SG on pile.	Private aid 1
	5375	- LIGHT 4		FI R 45	14		TR on pile.	Private aid.
	5380	- LIGHT 5	37 50.6 122 18.5	FI G 45	14		SG on pile.	Private aid.
	5385	- LIGHT 6		FI R 45	14		TR on pile.	Private aid.
	5390	- LIGHT 7	37 50.5 122 18.6	Iso G 45	17		SG on pile.	Private aid.



# FEDERICO R. DIAZ CHIEF OF PARTY (HYDROGRAPHER, GEODESIST)





U.S. DEPARTMENT OF COMMERCE National Oceanic and Atmospheric Administration NATIONAL OCEAN SERVICE

PACIFIC HYDROGRAPHIC PARTY 614-A East 5TH Street Benicia, CA 94510

19 January 1988

N/MOP223:frd

U.S. Department of Commerce sational Oceanic & Atmospheric Administration PACIFIC HYDROGRAPHIC PARTY

≠ Albeit (207) 246 8189

ATTEN: Maggie McHugh BRISBANE MARINA 400 Marina Blvd. Brisbane, CA 94005

Dear Maggie,

As promised in late October 1987, I am submitting a smooth copy of our survey to verify the existance of the charted 4-ft channel leading into the vicinity of the Brisbane Marina. The survey soundings are plotted at Mean Lower Low Water (MLLW) tidal datum, using predicted tides.

As one can see, the survey depths are at least 3-ft deeper than is shown on the chart (copy attached). The shoalest depth, leading into the Brisbane Marina, is 7 feet. This would be the new controlling depth. The new edition of Chart #18651 will indicate the new controlling depth, once the survey has been verified and compliled by NOAA Nautical Chart Division in Rockville, MD.

The controlling depth leading into the Oyster Point Marina has changed. The chart shows "2 ft rep 1983". Survey depths show least depths of 8 to 9 feet. A difference of 6 feet. These changes should be indicated on the next edition of Chart # 18651, which should be available for distribution in later 1988 (hopefully).

The data submitted is subject to change and should not be used for navigational purposes.

I apologize for the delay in submitting this data. The PACIFIC HYDROGRAPHIC PARTY (PHP) would like to appreciate Brisbane Marina for all the assistance and support given to us during the survey. For questions and/or requests please write or call (707) 746-8189. THANKS!


SINCERELY.

\* BRISBANE MARINA ENTRANCE CHANNEL

Federico R. Diaz

Chief, PHP





## ITEM #168



### U.S. DEPARTMENT OF COMMERCE National Oceanic and Atmospheric Administration

NATIONAL OCEAN SERVICE PACIFIC HYDROGRAPHIC PARTY 614-A East 5TH St. Benicia, CA 94510

18 November 1987

Mr. Mike Lind Vice President JERICO DREDGING, INC. 100 East D St. Petaluma, CA 94952

Dear Mr. Lind:

On 07 November 1987 the Pacific Hydrographic Party (PHP) was conducting hydrographic survey operations at Latitude 37 37'43"N, Longitude 122°15'34"W southeast of San Bruno Shoal and north of the San Mateo Bridge, sounding a 10-foot shoal in approximately 14 to 18 feet of water.

On the following day, a dredge of JERICO DREDGING INC, was observed conducting dredging operations at or near the above geographic location.

The PHP is presently conducting sounding operations in the South San Francisco Bay to upgrade the existing nautical charts of the area.

In a phone conversation with Mr. Jerry Morris on 17 November, he indicated that JERICO DREDGING is presently dredging for oyster shells within the area of interest about two days a week.

At this point, there are slight differences between the present survey depths and charted depths. The bottom shows signs of scouring within the area mentioned above, but is known to be dynamic in nature.

We request a memo from your office verifying dredging operations at the geographic location of interest, as this would help us process existing field sounding data through our verification headquarters in Seattle, Washington. Also, enclosed is a chartlet of the area. We request that your office outline the actual area being dredged as this will be helpful to the mariner on the next edition of Chart #18651.

For questions, please call (707) 746+8189. Your cooperation in this matter is appreciated.

Sincerely,

Federico R, Díaz

Chief, PHP



## JERICO DREDGING. INC.

100 EAST "D" STREET • PETALUMA CA 94952 • (707) 762-7251

#168

**DECEMBER 1, 1987** 

MR. FEDERICO DIAZ CHIEF, PHP NATIONAL OCEAN SERVICE 614-A EAST 5TH STREET BENECIA, CA 94510

DEAR MR. DIAZ,

AS PER YOUR REQUEST OF NOVEMBER 18, 1987 I HAVE OUTLINED THE AREA THAT WE DREDGE OYSTER SHELL ON THE CHART YOU PROVIDED.

IF YOU NEED ANY FURTHER ASSISTANCE PLEASE LET ME KNOW.

SINCERELY,


MICHAEL LIND VICE-PRESIDENT


AL/CT

CT


\* 1

- V. Lie





100-METER RADIUS BOTTOM CIRCLE DRAG SET UP



DRAWING NOT TO SCALE

WIRE DRAG CONFIGURATION

FIGURE 2



U.S. DEPARTMENT OF COMMERCE
National Oceanic and Atmospheric Administration
NATIONAL OCEAN SURVEY

PACIFIC HYDROGRAPHIC PARTY - NOAA 1A UCCELLI BLVD. REDWOOD CITY, CA 94063

11 August, 1983

TO:

N/MOP21 - Ned C. Austin

THRU:

N/MOP - Charles K. Townsend

FROM:

N/MOP223 - Pamela R. Chelgren

SUBJECT: Pre-Processing Critique of H-9984, dated 7/20/83

Section II.C., paragraphs 4 and 5 of the critique maintain that the wide beam fathometer search for the least depths under the San Mateo - Hayward Bridge was insufficient. Our considered belief is that it was adequate and we did find the least depths. Our judgment is based on the facts that: 1) the 45° beam gave us a swath of 8 meters in 38 feet of water (unreduced); 2) besides the 10-meter spaced lines run, there were two 2-hour extensive drift searches that were easily controlled between the bridge's main span and they most certainly gave us an effective coverage of better than 5 meters for that 8-meter swath; and 3) I have been informed in the past by several acoustical engineers (at Klein and Raytheon) that the wider a transducer beam gets the less and less it looks like a narrow beam trace on peaks and deeps. I am convinced that the copy of the fathogram that was appended to the critique showed a least depth for our wide beam. I therefore feel the search was complete and adequate.

Other search methods were ruled out because of the strong and eddying currents, and the zero-foot water visibility. There is no such thing as slack current at the main span of the bridge. Instead it weakens and develops unpredictable eddies, and then changes direction. Diving operations would have been unsafe. A small-boat wire/chain drag would have been ineffective and inconclusive. (The rig would ride up over the clay and silt ridges in that eddying current.) Note: USGS gave us the bottom character-

istic. They conduct geological studies of the extensive sediment plumes at the bridge.

The raw data records on this investigation are in the Cahier for JD's 087, 097, and 150/1983. Our discussions in the Descriptive Report are contained in Section K/H-8275/Soundings/Item 2; Section L/Soundings/Item 4; Section L/Investigation E; and the two paragraphs immediatley following the list of investigations.

cc: N/MOP22

H-9984 Descriptive Report

N/CG24

ITEM 169



#### FROM DESCRIPTIVE REPORT H-9984

## Non-sounding Features.

The San Mateo Bridge Transmission Towers still exist as depicted on prior survey H-8027.

H-8275, 1:10,000 Scale, 1956.

## Soundings.

Prior survey H-8275 has an agreement of  $^{\pm}$  2 feet with survey H-9984 (allowing a positional shift of  $^{\pm}$   $^{1}$ 2 mm) except for the following:

- 1. The area around the sewer pipeline south of the San Mateo-Hayward Bridge (latitude 37°34'30"N, longitude 122°15'28"W) is deeper by up to 5 feet than shown on survey H-8275 (see development G). It is probable that the change in this area was caused by the dredging done to lay the pipeline. It is recommended that survey H-9984 be used to update the chart.
- 2. The area just northwest and southeast (within 0.1 Nm) of the San Mateo-Hayward Bridge in, and around, the main ship channel has deepened up to 10 feet in some areas and shoaled up to 14 feet in others in a location with depths of 34 to 51 feet. There is evidence on the fathograms of some scouring. Telephone conversations with Dave Rubin and Dave McCulloch, Geologists, U.S. Geological Survey, Menlo Park, California, (415) 856-7103 confirmed this. They stated that there are sediment plumes extending away from the San Mateo-Hayward Bridge, there is localized scouring and ridges in their side scan sonar records, the grain size of the sediment is in the silt and clay categories (finer than sand), and that this condition has existed for the last five years probably because of the abnormally large tides California has been experiencing during this time. It is recommended that survey H-9984 be used to update the chart.
  - 3. The bank on the notheast side of the main ship channel, just southeast of the San Mateo-Hayward Bridge (latitude 37 35.4'N, longitude 122 14.3'W) and extending northeast to the east edge of the survey sheet has deepened 2 to 4 feet out to the 12 foot contour. On prior survey H-8275 it is shown as uncovering 1 foot; now the least depth is 2 feet and no bare spots were observed on a minus 1 foot tide. This deepening was probably caused by the dredging of the sand and shell banks immediately north of the San Mateo-Hayward Bridge which allowed the two knot currents experienced here to erode the shoal spots. It is recommended that survey H-9984 be used to update the chart.

Additional investigation should have been conducted to ensure that the least depth was observed.

\*ITEM 170 A holiday exists on the north side of the San Mateo - Hayward Bridge (Attachment B).

Names of horizontal control stations on field sheets should be consistent with station names contained in or submitted for entry to the NGS data base. The year of establishment is part of the station name for stations established before January 1977, as "GUANO ISLAND 1851". For stations established after January 1977 the year of establishment supplements the station name and should be separated from it by a comma or parentheses, as "BLOCK 2, 1982" or "BLOCK 2 (1982)". Section 2.2.04.3 of the NGS Operations Manual is the reference for naming horizontal control stations.

Field sheet notes are well done.

## D. Descriptive Report

The Descriptive Report is well done, except that section A (Project) does not acknowledge all changes to the project instructions.

The inclusion of photographs of specific items investigated or observed, including pipes, piles, poles, etc., is excellent.

## E. Echograms

Echograms are well maintained and annotated. Echosounder checkout frequency and procedures generally satisfied PMC OPORDER requirements.

## F. Sounding Volumes and Raw Data Printouts

Field data were generally well annotated and complete. Cross references to precedent and subsequent investigations in a common area are excellent.

Two deficiencies were noted in association with range-azimuth operations:

- 1. The observing station was not identified on one occasion.
- 2. Check initials were not observed. Check initials are required by section 4.4.4 of the Hydrographic Manual.

## N. Survey Acceptance

The preprocessing examination for H-9984 was conducted under the time constraints of Hydrographic Survey Guideline No. 15. All comments contained herein are based on a spot check of the data, and it is likely that some problem areas have not been addressed.

Commander Eleventh Coast Guard District

ITEM 188 AWOIS 51147 Building 10, Rm 214 Coast Guard Island Alameda, CA 94501-5100 Staff Symbol: (oan) (415) 437-3514

16591 San Francisco Bay (32.0) 5 February 1988

Mr. Burch C. Bachtold Director CALTRANS District 4 150 Oak Street San Francisco, CA 94102

Dear Mr. Bachtold:

The Coast Guard and the National Ocean Survey recently inspected the Dumbarton Highway Bridge. The bridge is still displaying some temporary navigation lights which had been installed to guide vessels through both the old and new bridges during the construction phase. The four red margin of channel lights on the soffit are the temporary lights. Since the permanent pier lights are in place, the temporary lights should be removed or turned off.

The National Ocean Survey found several submerged obstructions at the site of the old Dumbarton Bridge main navigation channel piers/pier fenders. The enclosed letter describes their survey and provides a point of contact. The material found was chunks of concrete which must have been part of the old bridge overlooked during removal operations. Your Coast Guard bridge permit specifies that all parts of the old bridge were to be removed to the natural bottom of the waterway. Please submit a plan and schedule for removal of the bridge debris. Since the removal was a condition of your permit, no additional approvals are required for the work except normal Coast Guard review of work in navigable channels.

Sincerely,

W. R. TILL Chief, Bridge Section North By direction of the District Commander

Encl: (1) NOS 1tr dtd 16 DEC 87

(2) Bridge permit amendment 138-74a-12

Copy to: NOS Survey Party Benicia 🗸

USCG District 11

USCG Marine Safety Office SF

USCGAUX Jim Duncan

## Department of Transportation United States Coast Guard

## UNITED STATES GOVERNMENT MEMORANDUM

5 February 1988 16500/16591

Subj: ITEM FOR LOCAL NOTICE TO MARINERS

From: (oan-br-n)

To: (oán)

Ref: (a) My 1tr to CALTRANS dtd 5 FEB 88

(b) NOS 1tr dtd 16 DEC 87

1. The NOS Survey party reported finding submerged obstructions at the site of the former Dumbarton Highway Bridge navigation channel piers. I have notified CALTRANS to remove the material. Please publish the following item in the LNM 7/88 and quarterly until the material is removed:

NORTHERN CALIFORNIA - SAN FRANCISCO BAY - DUMBARTON BRIDGE. The National Ocean Survey has found submerged obstructions at the location of the former Dumbarton Highway Bridge main navigation channel piers at Lat. 37-30-11.5N, Long. 122-07-15.8W and Lat. 37-30-24.3N, Long. 122-06-56.6W. There are no obstructions in the federal channel through the site.

Charts: 18651, 18652

W. R. TILL

Copy to: NOS Survey Party Benicia

## SURVEY/CHARTING REQUEST DOCUMENTATION

TO: N/CG2	
FROM: N/MOP223	
SUBJECT: Request for Survey XXXXXXXXXX	
Today I was visited by:	
Name: Robert J. Guinn	<del></del>
Title: Senior Engineer, Mainte	nance
Representing: California Departm	ent of Transportation (CALTRANS)
Phone Number: (415) 557-0155 / 46	4-0359
Address: P.O. Box 7310	(Street or Number)
San Francisco, CA	City
. 94120	Zip Code
This person requested that NOAA perform following area(s): Dumbarton Highway 1 37/30/16.70 N, 122/07/03	Bridge
This person believes that a survey except because:  Upon completion of the recovery of the old Dumbarton Highway Bridge, CA survey the area to ensure that all debut (Refer to Descriptive Report FE-311, AV	of the submerged debris in the vicinity ALTRANS requests an NOS Survey Party ris has been cleared to the mudline.
The above request is an accurate and varequest received by:  Telcon: 5/50/89 with Mr Gumn indicated  that no removal as of this date has  been accomplished. RWD	Name/Title: Federico R. Diaz Chief. PHP Signature: R.
	Date: 04/13/88

DEC 8



## U.S. DEPARTMENT OF COMMERCE National Oceanic and Atmospheric Administration

NATIONAL OCEAN SERVICE

PACIFIC HYDROGRAPHIC PARTY 614-A East 5TH Street Benicia, CA 94510

14 December 1987 N/MOP223:FRD

TO:

N/MOP

- Robert L. Sandquist

THRU:

N/MOP21 - Thomas W. Richards

FROM:

N/MOP223 - Federico R. Díaz Federa

SUBJECT: Request for extension of data submission for Field Examinations of Chart Numbers 18650 and 18651.

Field work for Field Examinations for Chart Numbers 18650 and 18651 were completed on 01 December and 17 November 1987, respectively.

The PACIFIC HYDROGRAPHIC PARTY requests extensions of data submission for both surveys until 31 January 1988.

The reasons for this request for extensions are:

- Large quantities of data acquisition, and lack of a full compliment of personnel for processing. (Should be six people; at present two people short).
- Survey preparations for OPR-L202-PHP-88, Carquinez Strait, CA, to begin field operations by early to mid January 1988.
- At present, PHP's Survey Launch 1101 is in the yard for its annual winter haul-out, which requires the attention of the party chief and engineering technician.

Your cooperation is appreciated.

I concor with extension OK- John 12/17/87 Two 12/17/87

Approved:

Robert L. Sendquist

Date

Date

Disapproved:

Robert L. Sandquist

NOAR



The second of th

#### U.S. DEPARTMENT OF COMMERCE National Oceanic and Atmospheric Administration NATIONAL OCEAN SERVICE

PACIFIC HYDROGRAPHIC PARTY 614-A East 5TH Street Benicia, CA 94510

22 January 1988

N/MOP223:frd

TO:

- Robert L. Sandquist

mir LI

21

THRU:

- Thomas W. Richards

FROM:

N/MOP223 - Federico R. Díaz falletis /

SUBJECT:

Request for second extension of data submission for field examinations

of Charts #18650 and 18651.

Field work for both field examinations\_are 100% complete. Presently, PHP personnel (three people) are completing the descriptive reports; annotating the smooth field sheets for both field exams, having extensive aluminium clad welding and bottom painting on Launch 1101 performed, repairing and tuning all electronic/mechanical equipment to begin field operations.

The PACIFIC HYDROGRAPHIC PARTY requests extensions of data submission of both field exams until 29 February 1988 for the following reasons:

- I reported to the PHP about mid-October 1987. Field work for Field Exam of Chart 18650 was nearly complete. It is my feeling that if I am to approve the survey, all field work, prior to my arrival, should be inspected for completion. Field work for this field exam began in mid-May 1987 and was completed 01 December 1987. The final inspection for completion took longer than originally anticipated.
- At present, PHP personnel is down to two commissioned officers and one engineering tech. With the loss of survey and cartographic techs, processing and annotation of smooth field sheets has become slow and cumbersome. It will remain a "push" to complete these surveys by the end of February.

Due to the limitation of personnel, survey preparations for OPR-L202-PHP-88, Carquinez Strait, CA has temporarily come to a halt. All of our attention is on completion of these two field exams and gearing up Launch 1101 for field work.

Your cooperation is appreciated.

1st Endorsement: I concur with extension.

N/MOP21/22

Extension approved:



#### Approval Sheet

### OPR-L123-PHP-87

### Field Examination Southern San Francisco Bay

The Chief of Party has inspected all field data on a weekly basis. All reports and records are complete. This survey is adequate for charting purposes and no additional field wbrk is necessary.

Approved by:

LT Federico R. Díaz, NOAA

CHIEF

PACIFIC HYDROGRAPHIC PARTY NATIONAL OCEAN SERVICE (NOS)

# U.S. DEPARTMENT OF COMMERCE NATIONAL OCEANIC AND ATMPOSPHERIC ADMINISTRATION NATIONAL OCEAN SERVICE

## TIDE NOTE FOR HYDROGRAPHIC SURVEY

DATE: January 25, 1988

MARINE CENTER: Pacific

OPR: L123

HYDROGRAPHIC SHEET: Field Examination of Chart 18651 FE-3//

LOCALITY: Oyster Point to Dumbarton Point, San Francisco Bay, CA

TIME PERIOD: November 4 - 16, 1987

TIDE STATION(S) USED: 941-4458 San Mateo Bridge, CA

941-4750 Alameda, CA

PLANE OF REFERENCE (MEAN LOWER LOW WATER): 941-4458 = 14.66 ft. 941-4750 = 3.27 ft.

HEIGHT OF HIGH WATER ABOVE PLANE OF REFERENCE: 941-4458 = 7.0 ft. 941-4750 = 5.9 ft.

## REMARKS: RECOMMENDED ZONING

- 1. For AWOIS Items 173, 174, 176, zone direct on 941-4750.
- For AWOIS Items 151, 160, 162, 166, 167, 50781, 50782, zone on 941-4750 and apply a +0 hr 15 minute time correction and a X1.11 range ratio to all heights.
- 3. For AWOIS Items 168, 169, 170, zone direct on 941-4458.
- 4. For AWOIS Item 51147 zone on 941-4458 and apply a +0 hr 20 minute time correction and a X1.13 range ratio to all heights.

CHIEF, TIDAL DATUM QUALITY ASSURANCE SECTION

NOAA FORM 76-155 (11-72) NATI	GEOGRAPHIC NAMES				s Su	SURVEY NUMBER FE-311			
GEOG									
Name on Survey	A ON CHART I	0. 1865	UP WEY	ANGLE ON ORMAT	JOH LOCAL W	Pro Gulos	OR WARP	U.S. LIGHT	J.197
CALIFORNIA (title)									1
LITTLE COYOTE POINT									2
OYSTER POINT									3
SAN BRUNO, POINT									4
SAN FRANCISCO BAY									5
SIERRA POINT									6
									7
								v	8
								,	9
									10
									11
·									12
									13
									14
									15
									16
									17
·			Appro	ved;					18
			7				,		19
			Ch	arlia.	F. B	am	nglo	72	20
-			Chief	Gecgra	nher _	N/CG:	2,5	-	21
			APR	121	988				22
									23
					<u> </u>			-	
									24
NOAA FORM 76-155 SUPERSEDES C&	G8 197	L			L	L	<u> </u>	1	25

HYDROGRAPHIC SURVEY STATISTICS  RECORD SACCOMPANYING SURVEY To the companied who survey a processor.  RECORD DESCRIPTION AMOUNT RECORD DESCRIPTION AMOUNT RECORD DESCRIPTION AMOUNT SMOOTH SHEET S SMOOTH OVERLAYS; POS., ARC, EXCESS 5  SMOOTH OVERLAYS; POS., ARC, EXCESS 5  SESCRIPTIVE REPORT 1 FIFLD SHEETS AND OTHER OVERLAYS 3  DESCRIPTIVE REPORT 1 FIFLD SHEETS AND OTHER OVERLAYS 3  DESCRIPTIVE REPORT 1 FIFLD SHEETS AND OTHER OVERLAYS 3  ACCORDION 1 RECORDS HORIZ CONT RECORDS HORIZ CONTROL SWALL CONTROL SW	NOAA FORM 77 (9-83)	'-27(H)		U.S. DEPARTME	ENT OF COMMERCE	REGIST	'RY NUMBE	R
RECORD DESCRIPTION AMOUNT SMOOTH SHEET 5 SMOOTH OVERLAYS: POS., ARC. EXCESS 5 DESCRIPTIVE REPORT 1 FIELD SHEETS AND OTHER OVERLAYS 3  DESCRIPTIVE REPORT 1 FIELD SHEETS AND OTHER OVERLAYS 3  DESCRIPTIVE REPORT RECORDS HORIZ CONT. RECORDS GRAMS PRINTOUTS SOURCE COUNTRY FION RECORDS HORIZ CONT. RECORDS GRAMS PRINTOUTS SOURCE COUNTRY FION RECORDS GRAMS PRINTOUTS SOURCE COUNTRY FION RECORDS GRAMS PRINTOUTS ASSTRACTS GRAMS PRINT						FI	E-311	
SMOOTH SHEET 5 SMOOTH OVERLAYS: POS., ARC, EXCESS 5 DESCRIPTIVE REPORT 1 1 FIELD SHEETS AND OTHER OVERLAYS 3 DESCRIPTIVE REPORT RECORDS RECORDS GRAMS PRINTOUTS ASSURED SOURCE PRINTOUTS TO THE PRINTOUTS OF THE PRINTOUTS ASSURED SOURCE PRINTOUTS AS	RECORDS AC	COMPANYING SUF	RVEY: To be completed to	when survey is processed	1.	<u> </u>		
SMOOTH SHEET 5 SMOOTH OVERLAYS: POS. ARC, EXCESS 5 DESCRIPTIVE REPORT 1 FIELD SHEETS AND OTHER OVERLAYS: 3 DESCRIPTIVE REPORT 1 FIELD SHEETS AND OTHER OVERLAYS: 3 DESCRIPTION RECORDS RECORD RECORDS RECORDS RECORD RECORDS RECORD RE	RECO	RD DESCRIPTION	AMOUN	Γ .	RECORD DESCRIP	PTION		AMOUNT
DESCRIPTIVE REPORT  DESCRIPTON  DESCRIPTON  RECORDS  RECO	SMOOTH SHE	EET	5	SMOOTH C	VERLAYS: POS., AR	C. EXCE	ss	
DESCRIP. RECORDS HORIZ CONT. SONAR GRAMS PRINTOUTS SOURCE COCCUMENTS  ACCOMPTION RECORDS 1	DESCRIPTIVE	REPORT			····			
ACCORDON FRES  INVOLIMES  VOLUMES  VOLUMES  VOLUMES  VOLUMES  VOLUMES  VOLUMES  VOLUMES  NOTICE PROCESSED  SHORELINE DATA  SHORELINE DATA  SHORELINE DATA  SHORELINE DATA  SHORELINE DATA  SHORELINE MAPS Liqui  NOTES TO THE HYDROGRAPHER (LIR)  SPECIAL REPORTS (LISS):  PROCESSING ACTIVITY  PROCESSING ACTIVITY  PROCESSING ACTIVITY  PROCESSING ACTIVITY  PROCESSING ACTIVITY  PROCESSING REVISED  TIME-HOURS  VERIFICATION  VERIFICATION OF PROTOBATHYMETRY  SHORELINE APPLICATION/VERIFICATION  VERIFICATION OF MADONIN SHEET  COMPARISON WITH PRIOR SURVEYS AND CHARTS  VERIFICATION OF SOURD SHEET  COMPARISON WITH PRIOR SURVEYS AND CHARTS  VERIFICATION OF MADONIN SHEET  COMPARISON WITH PRIOR SURVEYS AND CHARTS  VERIFICATION OF MADONIN SHEET  COMPARISON WITH PRIOR SURVEYS AND CHARTS  VERIFICATION OF MADONIN SHEET  COMPARISON WITH PRIOR SURVEYS AND CHARTS  VERIFICATION OF MADONIN SHEET  COMPARISON WITH PRIOR SURVEYS AND CHARTS  VERIFICATION OF MADONIN SHEET  COMPARISON WITH PRIOR SURVEYS AND CHARTS  VERIFICATION OF SURVEYS AND SWEEPS  VERLULATION OF WITH CHARGE OF MADONIN SHEET  COMPARISON WITH PRIOR SURVEYS AND CHARTS  VERIFICATION OF SURVEYS AND SWEEPS  VERLULATION OF WITH CHARGE OF MADONIN SHEET  COMPARISON WITH PRIOR SURVEYS AND CHARTS  VERIFICATION OF SURVEYS AND CHARTS  VERIFICATION OF SURVEYS AND SWEEPS  VERLULATION OF WITH CHARGE OF MADONIN SHEET  COMPARISON WITH PRIOR SURVEYS AND CHARTS  VERIFICATION OF SUR				SONAR-		ABST SO	URCE	
VOLIMES CAMERS C		1					MENTS	
CAHERS  SHORELINE DATA  SHORELINE MAPS (LIB):  PHOTOSATHYMETRIC MAPS (LIB):  PHOTOSATHYMETRIC MAPS (LIB):  SPECIAL REPORTS (LIS):  NAUTICAL CHARTS (LIS):  5 paper enlargement of chart 8651, 52nd Edition  OFFICE PROCESSING ACTIVITIES  The holipowing stealists will be submitted with the carbographor's report on the auriery  PROCESSING ACTIVITY  PROCESSING ACTIVITY  PROCESSING REPORTS (LIS):  POSITIONS ON SHEET  POSITIONS ON SHEET  POSITIONS REVISED  COUNTROL STATIONS REVISED  CONTROL STATIONS REVISED  TIME-HOURS  VERIFICATION  VERIFICATION OF POSITIONS  39  39  39  39  183  183  183  183  18	ENVELOPES							
BOXES SHORELINE DATA SHORELINE MAPS (LIMI) SHORELINE MAPS (LIMI) MOTES TO THE HYDROGRAPHER (LIMI):  NOTES TO THE HYDROGRAPHER (LIMI):  The Moleving statistics will be submitted with the statistics of the funding statistics will be submitted with the stating paths in proof on the survey  PROCESSING ACTIVITY  PROCESSING ACTIVITY  PROFITCATION	VOLUMES	,						
SHORELINE DATA  SHORELINE MAPS (List):  NOTES TO THE HYDROGRAPHER (List):  NAUTICAL CHARTS (List):  NAUTICAL CHARTS (List):  The kollowing statistics will be submitted with the carbographer's report on the survey.  PROCESSING ACTIVITY  PROCESSING ACTIVITY  PROCESSING ACTIVITY  PROCESSING ACTIVITY  PROCESSING ACTIVITY  PROCESSING ACTIVITY  POSITIONS ON SHEET  POSITIONS ON SHEET  POSITIONS REVISED  SOUNDINGS REVISED  TIME-HOURS  VERIFICATION  VERIFICATION  VERIFICATION  VERIFICATION  VERIFICATION OF CONTROL  VERIFICATION OF POSITIONS  183  183  183  VERIFICATION OF JUNCTIONS  APPLICATION OF SURVEYS AND CHARTS  EVALUATION OF SIDE SCAN SONAR RECORDS	CAHIERS	,						
SHORELINE MAPS (List): PHOTOBATHYMETRIC MAPS (List): NOTES TO THE VIPODOGARPHER (List): SPECIAL REPORTS (List): NAUTICAL CHARTS (List): SPECIAL REPORTS (List): NAUTICAL CHARTS (List):  The Mollowing statistics with be submitted with the carbog applier's report on the survey  PROCESSING ACTIVITY  PROCESSING ACTIVITY  PROPERTY OF THE PROCESSING ACTIVITY  POSITIONS ON SHEET POSITIONS ON SHEET POSITIONS ON SHEET POSITIONS REVISED  CONTROL STATIONS REVISED  CONTROL STATIONS REVISED  TIME-HOURS  VERIFICATION VERIFICATION VERIFICATION VERIFICATION VERIFICATION VERIFICATION VERIFICATION VERIFICATION OF POSITIONS VERIFICATION OF POSITIONS VERIFICATION OF POSITIONS VERIFICATION OF PROPERTY OF PROPERTY VERIFICATION OF PROPERTY VERIFICATION OF PROPERTY	BOXES							
SHORELINE MAPS (List): PHOTOBATHYMETRIC MAPS (List): NOTES TO THE VIPODOGARPHER (List): SPECIAL REPORTS (List): NAUTICAL CHARTS (List): SPECIAL REPORTS (List): NAUTICAL CHARTS (List):  The Mollowing statistics with be submitted with the carbog applier's report on the survey  PROCESSING ACTIVITY  PROCESSING ACTIVITY  PROPERTY OF THE PROCESSING ACTIVITY  POSITIONS ON SHEET POSITIONS ON SHEET POSITIONS ON SHEET POSITIONS REVISED  CONTROL STATIONS REVISED  CONTROL STATIONS REVISED  TIME-HOURS  VERIFICATION VERIFICATION VERIFICATION VERIFICATION VERIFICATION VERIFICATION VERIFICATION VERIFICATION OF POSITIONS VERIFICATION OF POSITIONS VERIFICATION OF POSITIONS VERIFICATION OF PROPERTY OF PROPERTY VERIFICATION OF PROPERTY VERIFICATION OF PROPERTY	SHORELINE D	DATA ////////						
NOTES TO THE MORPOGRAPHER (LUSI):  SPECIAL REPORTS (LUSI):  NAUTICAL CHARTS (LUSI):  Spaper enlargement of chart 8651, 52nd Edition  OFFICE PROCESSING ACTIVITY  PROCESSING ACTIVITY  PROCESSING ACTIVITY  PROCESSING ACTIVITY  PROCESSING ACTIVITY  AMOUNTS  VERIFICATION  FUALUATION 107ALS  POSITIONS ON SHEET  POSITIONS ON SHEET  POSITIONS REVISED  TIME-HOURS  VERIFICATION EVALUATION 107ALS  PROPER PROCESSING EXAMINATION  VERIFICATION OF CONTROL  VERIFICATION OF CONTROL  VERIFICATION OF POSITIONS  183  183  183  183  183  183  VERIFICATION OF POSITIONS  184  VERIFICATION OF JUNCTIONS  184  VERIFICATION OF JUNCTIONS  185  VERIFICATION OF JUNCTIONS  186  VERIFICATION OF POSITIONS  186  VERIFICATION OF SMOOTH SHEET  141  141  141  COMPARISON WITH PRIOR SURVEYS AND CHARTS  EVALUATION OF WITH PRIOR SURVEYS AND CHARTS  EVALUATION OF WITH PRIOR SURVEYS AND CHARTS  VERIFICATION OF WITH PRIOR SURVEYS AND CHARTS  VERIFI								
SPECIAL REPORTS (List):  NAUTICAL CHARTS (List):  The following statistics will be submitted with the carlographer's report on the survey  PROCESSING ACTIVITY  PROCESSING ACTIVITY  PROCESSING ACTIVITY  PROCESSING ACTIVITY  PROSITIONS ON SHEET  POSITIONS REVISED  CONTROL STATIONS REVISED  CONTROL STATIONS REVISED  CONTROL STATIONS REVISED  TIME-HOURS  VERIFICATION	PHOTOBATHYM	ETRIC MAPS (List):				·		
NAUTICAL CHARTS (List): 5 paper enlargement of chart 8651, 52nd Edition  OFFICE PROCESSING ACTIVITES  The following statistics will be submitted with the carbographer's report on the survey  PROCESSING ACTIVITY  PROCESSING ACTIVITY  AMOUNTS  VERIFICATION EVALUATION TOTALS  POSITIONS ON SHEET  POSITIONS REVISED  SOUNDINGS REVISED  SOUNDINGS REVISED  TIME-HOURS  TIME-HOURS  VERIFICATION PROPERTION  VERIFICATION OF POSITIONS  39  39  39  VERIFICATION OF POSITIONS  39  VERIFICATION OF SOUNDINGS  183  183  183  VERIFICATION OF JUNCTIONS  APPLICATION OF JUNCTIONS  APPLICATION OF JUNCTIONS  SHOPLINE APPLICATION VERIFICATION  COMPILATION OF SMOOTH SHEET  141  141  141  COMPARISON WITH PRIOR SURVEYS AND CHARTS  EVALUATION OF SIDE SCAN SONAR RECORDS  EVALUATION OF WITH CHARTS  VERIFICATION OF WITH CHARTS  VERIFICATION OF WITH CHARTS  VERIFICATION OF WITH CHARTS  VERIFICATION OF SIDE SCAN SONAR RECORDS  EVALUATION OF SIDE SCAN SONAR RECORDS  EVALUATION OF WITH CHARTS  VERIFICATION OF WITH CHARTS  VERIFICATION OF WITH CHARTS  VERIFICATION OF WITH CHARTS  VERIFICATION OF SIDE SCAN SONAR RECORDS  EVALUATION OF WITH CHARTS  VERIFICATION OF WITH CHARTS  VERIFICATION OF WITH CHARTS  VERIFICATION OF WITH CHARTS  VERIFICATION OF SIDE SCAN SONAR RECORDS  VERIFICATION OF WITH CHARTS  VERIFICA	NOTES TO THE	HYDROGRAPHER (List):			<u> </u>			
OFFICE PROCESSING ACTIVITY  PROCESSING ACTIVITY  PROCESSING ACTIVITY  AMOUNTS  VERIFICATION EVALUATION TOTALS  POSITIONS REVISED  CONTROL STATIONS REVISED  CONTROL STATIONS REVISED  VERIFICATION EVALUATION TOTALS  VERIFICATION EVALUATION TOTALS  PRE-PROCESSING EXAMINATION  VERIFICATION FOR POSITIONS  VERIFICATION FOR POSITIONS  VERIFICATION OF POSITIONS  VERIFICATION OF POSITIONS  39 39  VERIFICATION OF POSITIONS  VERIFICATION OF POSITIONS  VERIFICATION OF POSITIONS  APPLICATION OF POSITIONS  APPLICATION OF POSITIONS  APPLICATION OF SUNCTIONS  APPLICATION OF SIMPLE STANDAM RECORDS  EVALUATION OF SIMPLE SAND SWEEPS  EVALUATION OF WIPE DRAGS AND SWEEPS  EVALUATION OF WIP								
Time following statistics will be submitted with the cartographer's report on the survey	NAUTICAL CH	IARTS (List): 5	paper enlarg	ement of char	rt 8651, 52 <sub>nd</sub> 1	Edition	)	
PROCESSING ACTIVITY    VERIFICATION   EVALUATION   TOTALS			C	FFICE PROCESSING A	CTIVITIES			
POSITIONS ON SHEET  POSITIONS REVISED  SOUNDINGS REVISED  TIME-HOURS  TIME-HOURS  VERIFICATION  VERI				I be submitted with the c	rartographer's report on the s			<del>-</del>
POSITIONS ON SHEET  POSITIONS REVISED  SOUNDINGS REVISED  CONTROL STATIONS REVISED  TIME-HOURS  TIME-HOURS  VERIFICATION EVALUATION TOTALS  PRE-PROCESSING EXAMINATION  VERIFICATION OF POSITIONS  39 39  VERIFICATION OF POSITIONS  183 183  VERIFICATION OF SOUNDINGS  183 183  VERIFICATION OF JUNCTIONS  APPLICATION OF PHOTOBATHYMETRY  SHORELINE APPLICATION VERIFICATION  COMPLIATION OF SWOOTH SHEET  141 141  COMPLATION OF SWOOTH SHEET  141 16 16  16 16  16 16  VEX.ULATION OF SIDE SCAN SONAR RECORDS  EVALUATION OF WIRE ORAGS AND SWEEPS  EVALUATION OF FROM FOR REMARKS  TOTALS  363 71  PRE-PROCESSING EXAMINATION TIME CHARTS  TIME (HOURS)  For ORAGINATION OF SOUNDINGS  TIME (HOURS)  TIME (HOURS)  TIME (HOURS)  TIME (HOURS)  TIME (HOURS)  For ORAGINATION  TOTALS  TIME (HOURS)  FOR ORAGINATION  TOTALS  TIME (HOURS)  FOR ORAGINATION  TOTALS  TOTALS		PROCESS	ING ACTIVITY		1/50/5/045/04			
POSITIONS REVISED  SOUNDINGS REVISED.  CONTROL STATIONS REVISED  TIME-HOURS  VERIFICATION PROCESSING EXAMINATION  VERIFICATION OF CONTROL  VERIFICATION OF POSITIONS  39 39  VERIFICATION OF SOUNDINGS  183 183  VERIFICATION OF POSITIONS  APPLICATION OF PHOTOGRATHYMETRY  SHORELINE APPLICATION/VERIFICATION  COMPILATION OF SIDE SCAN SONAR RECORDS  EVALUATION REPORT  GEOGRAPHIC NAMES  OTHER DIGITIZATION  TUSE OTHER SIDE OF FORM FOR REMARKS  TOTALS  TOTALS  TOTALS  TOTALS  TIME-HOURS  TIME-HOURS  TIME-HOURS  183  39  39  39  39  39  39  39  41  41  41  41  41  41  41  41  41  4	POSITIONS ON SE	HEET			VERIFICATION	EVAL:	UATION	
SOUNDINGS REVISED.  CONTROL STATIONS REVISED  TIME-HOURS  PRE-PROCESSING EXAMINATION  PRE-PROCESSING EXAMINATION  VERIFICATION OF EVALUATION  VERIFICATION OF CONTROL  VERIFICATION OF POSITIONS  39  VERIFICATION OF POSITIONS  39  VERIFICATION OF POSITIONS  APPLICATION OF POSITIONS  APPLICATION OF PROTOBATHYMETRY  SHORELINE APPLICATION/VERIFICATION  COMPRIATION OF SMOOTH SHEET  141  141  141  COMPARISON WITH PRIOR SURVEYS AND CHARTS  EVALUATION OF SIDE SCAN SONAR RECORDS  EVALUATION OF WIRE DRAGS AND SWEEPS  EVALUATION OF SIDE OF FORM FOR REMARKS  TOTALS  TOTALS  363  71  Pre-processing Examination by  LT J. Miller  Verification of Field Date by  R. N. Mihallov  Seginning Date  2/19/88  Finding Date  3/30/88  Finding Date  3/30/88  Finding Date  3/2/88  Finding Date  3/2/88  Finding Date  3/2/88  Finding Date  3/2/88  Finding Date  6/20/88  Evaluation and Analysis by  C. R. Davies  Impection by  Impection by  Impection by  Imperitor by  Imperi				· · · · · · · · · · · · · · · · · · ·				764
TIME-HOURS  PRE-PROCESSING EXAMINATION PRE-PROCESSING EXAMINATION VERIFICATION EVALUATION TOTALS  PRE-PROCESSING EXAMINATION VERIFICATION OF CONTROL VERIFICATION OF CONTROL VERIFICATION OF POSITIONS 39 39 39 VERIFICATION OF SOUNDINGS 183 183 VERIFICATION OF JUNCTIONS APPLICATION OF POSITIONS APPLICATION OF HOTOBATHYMETRY SHORELINE APPLICATION/VERIFICATION COMPILATION OF SMOOTH SHEET 141 141 141 141 16 16 16 16 16 17 17 18 18 18 18 18 18 18 18 18 18 18 18 18								
TIME-HOURS  VERIFICATION EVALUATION TOTALS  PRE-PROCESSING EXAMINATION  VERIFICATION OF CONTROL  VERIFICATION OF POSITIONS  39  39  VERIFICATION OF POSITIONS  183  183  183  183  183  183  183  18								
PRE-PROCESSING EXAMINATION  VERIFICATION OF CONTROL  VERIFICATION OF CONTROL  VERIFICATION OF CONTROL  VERIFICATION OF POSITIONS  39  39  39  39  VERIFICATION OF SOUNDINGS  183  183  183  183  APPLICATION OF SUNDINGS  APPLICATION OF PHOTOBATHYMETRY  SHORELINE APPLICATION/VERIFICATION  COMPILATION OF SMOOTH SHEET  141  141  141  COMPARISON WITH PRIOR SURVEYS AND CHARTS  EVALUATION OF SIDE SCAN SONAR RECORDS  EVALUATION OF WIRE ORAGS AND SWEEPS  EVALUATION OF WIRE ORAGS AND SWEEPS  EVALUATION REPORT  355  555  GEOGRAPHIC NAMES  OTHER  OTHER SIDE OF FORM FOR REMARKS  TOTALS  Beginning Date  1.T. J. Miller  2/19/88  3/30/88  Fre-processing Examination by  R.N. Milhailov  Time (Hours)  33.0  Ending Date  33.0  Ending Date  6/20/88  Evaluation and Analysis by  C.R. Davies  Time (Hours)  350  Time (Hours)  150  Ending Date  6/20/88  Ending Date  71  Time (Hours)  71  Find Date  71  Time (Hours)  71  Time (	CONTROL STATIC	//////////////////////////////////////						
PRE-PROCESSING EXAMINATION  VERIFICATION OF CONTROL  VERIFICATION OF POSITIONS  39  39  VERIFICATION OF POSITIONS  183  183  VERIFICATION OF SOUNDINGS  183  VERIFICATION OF JUNCTIONS  APPLICATION OF JUNCTIONS  APPLICATION OF PHOTOBATHYMETRY  SHORELINE APPLICATION VERIFICATION  COMPILATION OF SMOOTH SHEET  141  141  141  COMPARISON WITH PRIOR SURVEYS AND CHARTS  EVALUATION OF SIDE SCAN SONAR RECORDS  EVALUATION OF WIRE DRAGS AND SWEEPS  EVALUATION OF WIRE DRAGS AND SWEEPS  EVALUATION REPORT  GEOGRAPHIC NAMES  OTHER DIGITIZATION  USE OTHER SIDE OF FORM FOR REMARKS  TOTALS  363  71  Pre-processing Examination by  LT J. M111er  Verification of Field Data by  R. N. Mihailov  Verification of Field Data by  R. N. Mihailov  Verification Check by S. Otsubo, B. Olmstead  Time (Hours) P/9/19/88  Inspection by D. J. Mills  Intelligence					VERIFICATION			
VERIFICATION OF POSITIONS   39   39   39     VERIFICATION OF SOUNDINGS   183   183     VERIFICATION OF JUNCTIONS   183   183     VERIFICATION OF PHOTOBATHYMETRY	PRE-PROCESSING	S EXAMINATION			VERMICATION	EVAL	DATION	IOTALS
VERIFICATION OF SOUNDINGS	VERIFICATION OF	CONTROL						
VERIFICATION OF SOUNDINGS  VERIFICATION OF JUNCTIONS  APPLICATION OF PHOTOBATHYMETRY  SHORELINE APPLICATIONIVERIFICATION  COMPILATION OF SMOOTH SHEET  141  141  141  COMPARISON WITH PRIOR SURVEYS AND CHARTS  EVALUATION OF SIDE SCAN SONAR RECORDS  EVALUATION OF WIRE DRAGS AND SWEEPS  EVALUATION REPORT  GEOGRAPHIC NAMES  OTHER DIGITIZATION  USE OTHER SIDE OF FORM FOR REMARKS  TOTALS  Pre-processing Examination by  LT J. Miller  LT J. Miller  Pre-processing Examination by  Verification of Field Data by  R.N. Mihailov  Firme (Hours)  S. Otsubo, B. Olmstead  Firme (Hours)  Firme (Hours)  C.R. Davies  Inspection by  C.R. Davies  Inspection by  LT J. Time (Hours)  Firme (Hours)	VERIFICATION OF	POSITIONS			39			30
VERIFICATION OF JUNCTIONS  APPLICATION OF PHOTOBATHYMETRY  SHORELINE APPLICATION/VERIFICATION  COMPILATION OF SMOOTH SHEET  COMPARISON WITH PRIOR SURVEYS AND CHARTS  EVALUATION OF SIDE SCAN SONAR RECORDS  EVALUATION OF WIRE DRAGS AND SWEEPS  EVALUATION REPORT  GEOGRAPHIC NAMES  OTHER DIgitization  'USE OTHER SIDE OF FORM FOR REMARKS  TOTALS  Pre-processing Examination by  LT J. Miller  Verification of Field Data by  R.N. Mihailov  Verification Check by  S. Otsubo, B. Olmstead  Evaluation and Analysis by  C.R. Davies  Imperition by  LT MILL  Imperition by  C.R. Davies  Imperition of Floory  Imperitions  Imperition of Floory  Time (Hours)  1 Ending Date  6/20/88  Ending Date  6/20/88  Ending Date  6/20/88	VERIFICATION OF	SOUNDINGS			<del></del>			
SHORELINE APPLICATION/VERIFICATION	VERIFICATION OF	JUNCTIONS						
COMPILATION OF SMOOTH SHEET  COMPARISON WITH PRIOR SURVEYS AND CHARTS  EVALUATION OF SIDE SCAN SONAR RECORDS  EVALUATION OF WIRE DRAGS AND SWEEPS  EVALUATION REPORT  GEOGRAPHIC NAMES  OTHER Digitization  "USE OTHER SIDE OF FORM FOR REMARKS  TOTALS  TOTALS  Beginning Date  LT J. Miller  Pre-processing Examination by  LT J. Miller  Pre-processing Examination of Field Data by  R.N. Mihailov  Fine (Hours)  S. Otsubo, B. Olmstead  Evaluation and Analysis by  C.R. Davies  Fine (Hours)  Time (Hours)  Poly 19/88  Ending Date  Ending Date  6/20/88	APPLICATION OF I	PHOTOBATHYMETRY						
COMPARISON WITH PRIOR SURVEYS AND CHARTS  EVALUATION OF SIDE SCAN SONAR RECORDS  EVALUATION OF WIRE DRAGS AND SWEEPS  EVALUATION REPORT  GEOGRAPHIC NAMES  OTHER Digitization  "USE OTHER SIDE OF FORM FOR REMARKS  Fre-processing Examination by LT J. Miller  Verification of Field Data by R. N. Mihailov  Verification Check by S. Otsubo, B. Olmstead  Evaluation and Analysis by C. R. Davies  Inspection by LT J. Mill Inspection Date (Hours) S. Davies  Ending Date S. Otsubo, B. Olmstead  Evaluation and Analysis by C. R. Davies  Imme (Hours) S. Ending Date S. Otsubo, B. Olmstead  Evaluation and Analysis by S. Otsubo, B. Olmstead  Evaluation and Analysis by C. R. Davies  Imme (Hours) S. Ending Date S. Otsubo, B. Olmstead  Evaluation and Analysis by S. Otsubo, B. Olmstead	SHORELINE APPLI	CATION/VERIFICATION						
EVALUATION OF SIDE SCAN SONAR RECORDS  EVALUATION OF WIRE DRAGS AND SWEEPS  EVALUATION REPORT  GEOGRAPHIC NAMES  OTHER Digitization  "USE OTHER SIDE OF FORM FOR REMARKS TOTALS 363 71  Pre-processing Examination by Ending Date 2/19/88 5/3/30/88  Verification of Field Data by R.N. Mihailov  Verification Check by S. Otsubo, B. Olmstead 5. Otsubo, B. Davies 71 5. Image (Hours) 5. Otsubo, B. Davies 71 5. Image (Hours) 6. Reding Date 9/19/88 5. Otsubo, B. Olmstead 5. Otsubo, B. Olmst	COMPILATION OF	SMOOTH SHEET			141	· · · · · · · · · · · · · · · · · · ·		141
EVALUATION OF WIRE DRAGS AND SWEEPS  EVALUATION REPORT  55  GEOGRAPHIC NAMES  OTHER' Digitization  USE OTHER SIDE OF FORM FOR REMARKS  TOTALS  Beginning Date 2/19/88  Time (Hours) 363  Fre-processing Examination by R.N. Mihailov  Verification of Field Data by R.N. Mihailov  Verification Check by S. Otsubo, B. Olmstead  Evaluation and Analysis by C.R. Davies  Time (Hours) 33.0  Ending Date 6/20/88  Finding Date 33.0  Ending Date 6/20/88	COMPARISON WIT	H PRIOR SURVEYS AND	CHARTS			16	<del></del>	
EVALUATION REPORT  GEOGRAPHIC NAMES  OTHER Digitization  'USE OTHER SIDE OF FORM FOR REMARKS  TOTALS  Beginning Date LT J. Miller  LT J. Miller  Verification of Field Data by R.N. Mihailov  Verification Check by S. Otsubo, B. Olmstead  Evaluation and Analysis by C.R. Davies  Inspection by Inspection Dy D. L. Will  Inspection Dy	EVALUATION OF S	SIDE SCAN SONAR RECOR	RDS				****	
GEOGRAPHIC NAMES  OTHER Digitization  USE OTHER SIDE OF FORM FOR REMARKS  Pre-processing Examination by LT J. Miller  Verification of Field Data by R. N. Mihailov  Verification Check by S. Otsubo, B. Olmstead  Ending Date 3/30/88  Fine (Hours) 363  Fine (Hours) 363  Fine (Hours) 33.0  Ending Date 9/2/88	EVALUATION OF V	VIRE DRAGS AND SWEEP	rs					
GEOGRAPHIC NAMES  OTHER Digitization  'USE OTHER SIDE OF FORM FOR REMARKS  TOTALS  Beginning Date 2/19/88  LT J. Miller  Verification of Field Data by R.N. Mihailov  Frequency S. Otsubo, B. Olmstead  Ending Date 3/30/88  Frime (Hours) 363  Frime (Hours) 363  Frime (Hours) 363  Frime (Hours) 370  Finding Date 6/20/88  Evaluation and Analysis by C.R. Davies  Frime (Hours) 71  Finde (Hours) 71  Finding Date 9/19/88  Fring Date 9/19/88	EVALUATION REPO	ORT				55		5.5
USE OTHER SIDE OF FORM FOR REMARKS  TOTALS  363  71  Pre-processing Examination by LT J. Miller  Verification of Field Data by R.N. Mihailov  Verification Check by S. Otsubo, B. Olmstead  Evaluation and Analysis by C.R. Davies  Totals  363  71  Beginning Date 2/19/88  Time (Hours) 363  Finding Date 6/20/88  Ending Date 6/20/88  Ending Date 6/20/88  Ending Date 6/20/88		MES						
Pre-processing Examination by LT J. Miller  Verification of Field Data by R.N. Mihailov  Verification Check by S. Otsubo, B. Olmstead  Ending Date 3/30/88  Fine (Hours) S. Otsubo, B. Olmstead  Ending Date 3/30/88  Ending Date 9/2/88  Finding Date 33.0  Ending Date 6/20/88  Evaluation and Analysis by C.R. Davies  Fine (Hours) 71  Fine (Hours) 9/19/88  Inspection by Finding Date 9/19/88								
LT J. Miller  Ventication of Field Data by R.N. Mihailov  Ventication Check by S. Otsubo, B. Olmstead  Evaluation and Analysis by C.R. Davies  Time (Hours) 363  Time (Hours) 33.0  Time (Hours) 33.0  Time (Hours) 71  Time (Hours) 71  Finding Date 6/20/88  Ending Date 6/20/88	· · · · · · · · · · · · · · · · · · ·		<u> </u>	TOTALS	363	71		
R.N. Mihailov  S. Otsubo, B. Olmstead  Evaluation and Analysis by C.R. Davies  Time (Hours)	LT	J. Miller	· · · · · · · · · · · · · · · · · · ·					88
S. Otsubo, B. Olmstead  Finding Date 6/20/88  Evaluation and Analysis by C.R. Davies  Time (Hours) 71  Finding Date 6/20/88  Ending Date 9/19/88  Inspection by Time (Hours) 71  Finding Date 9/19/88	R.N	. Mihailov					Ending Date	
C.R. Davies 71 9/19/88 Inspection by D. L. 11-11 Finding Date Time (Hours) Ending Date	S.	Otsubo, B. Oln	nstead	·			Ending Date	
Inspection by Time (Hours) Ending Date	C.R				1 ' '		9/19/	88
	D.J	. Hill			Time (Hours)		Ending Date	

## PACIFIC MARINE CENTER Evaluation Report FE-311

#### 1. INTRODUCTION

Survey FE-311 is a field examination accomplished by the Pacific Hydrographic Party under the following Project Instructions:

OPR-L123-PHP-87, dated February 10, 1987

CHANGE NO. 1, dated March 20, 1987

This field examination occurred in southern San Francisco Bay, California between Oyster Point and Dumbarton Point. The survey investigated ten unresolved AWOIS/Office Review Items originating from prior surveys. The results will be used to update chart 18651. Five separate surveyed areas extend from latitude 37°30'00"N, north to latitude 37°40'30"N and from longitude 122°07'00"W, west to longitude 122°23'20"W. The bottom slopes gradually from a shoreline consisting of numerous cultural features with marsh and mud flats to a maintained channel in the center of the bay. The bottom consists of mud and shells. Depths range from 0 feet nearshore to 52 feet in the dredged channel.

Predicted tides for Fort Point, California were used for the reduction of soundings during field processing. Approved hourly heights zoned from San Mateo Bridge and Alameda, gages 941-4458 and 941-4750 respectively, were used during office processing.

The field sheet parameters have been revised to center the hydrography on the smooth sheet and to change the projection to polyconic. The TRA, sound velocity and electronic control correctors are adequate. An accompanying computer printout contains the parameters and the correctors.

A digital file, generated for this survey, includes categories of information required to comply with N/CG2 Hydrographic Survey Guideline No. 23, Completion of Digital Hydrographic Surveys, September 7, 1983. Certain descriptive information, however, may not be in the digital record due to the restrictions of the presently available cartographic codes. The user should refer to the smooth sheet for complete information.

### 2. CONTROL AND SHORELINE

Sections F and G of the hydrographer's report and the Horizontal Control Report for OPR-L123-PHP-87 contain adequate discussions of horizontal control and hydrographic positioning.

Positions of horizontal control stations used during hydrography are 1987 field and published values based on NAD 27. These values were used during office processing for the computation of positions. The smooth sheet and accompanying overlays are annotated with NAD 83 adjustment ticks based on

values determined by N/CG121. Geographic positions based on NAD 83 may be plotted on the smooth sheet utilizing the NAD 27 projection by applying the following corrections:

latitude: 0.241 seconds (7.4 meters)
longitude: -3.887 seconds (-95.3 meters)

The year of establishment of control stations shown on the smooth sheet originates with hydrographer's signal list and is subject to change pending certification of the data by NGS.

There are no weak fixes (angles of intersection less than 30 degrees or more than 150 degrees) noted in this survey.

Contemporary shoreline maps are not available for this survey. Shoreline information originates from chart 18651, 35th Edition, dated July 5, 1986, scale 1:40,000 and is shown in brown on the smooth sheet for orientation purposes only.

Two shoreline changes are found on sheet 4 of 5. The old Dumbarton Bridge limits (east end) were located at latitude 37°30'24.37"N, longitude 122°06'56.57"W. The change is depicted as approximate since position fixes were taken on the offshore end of the bridge remains. The western portion of the bridge remains were located at latitude 37°30'11.52"N, longitude 122°07'15.79 "W. Both these changes represent significant differences from that presently charted.

#### HYDROGRAPHY

Hydrography is adequate to:

- a. delineate the bottom configuration, determine least depths, and draw the standard depth curves;
- b. reveal there are no significant discrepancies or anomalies requiring further investigation; and
- $\ensuremath{\mathtt{c}}.$  show the survey was properly controlled and soundings are correctly plotted.

#### 4. CONDITION OF SURVEY

The hydrographic records and reports received for processing are adequate and conform to the requirements of the Hydrographic Manual, 4th Edition, revised through Change No. 3; the Hydrographic Survey Guidelines; and the PMC OPORDER.

#### 5. JUNCTIONS

Junctions were not required by the Project Instructions. A comparison with charted depths reveals good agreement with the present survey.

#### COMPARISON WITH PRIOR SURVEYS

H-9819 (1979) 1:10,000 H-9872 (1980) 1:10,000 H-9952 (1981-82) 1:10,000 H-9984 (1981-83) 1:10,000 H-10132 (1984-85) 1:10,000

The AWOIS/Office Review Items investigated during this field examination were either carried forward to the above surveys from 1950 vintage surveys or were recommended for additional field work. Each of these AWOIS/Office Review Items are discussed, completely and adequately in section L of the hydrographer's report.

Survey FE-311 is adequate to supersede the prior surveys within the common area.

#### 7. COMPARISON WITH CHART

Chart 18651, 35th Edition, dated July 5, 1986; scale 1:40,000.

## a. Hydrography

Charted information originates with the prior surveys mentioned in section 6 of this report and from miscellaneous sources. For more details see section L of the hydrographer's report.

Survey FE-311 is adequate to supersede charted hydrography within the common area.

#### b. AWOIS

There are no AWOIS items originating from miscellaneous sources applicable to this survey.

### c. Controlling Depths

The charted 4-foot shoaling of the channel beginning at latitude 37°40'20"N, longitude 122°22'07"W was investigated. Mid-channel depths of 7 to 11 feet were observed, however, edge shoaling of 4 feet was detected in the vicinity of latitude 37°40'10"N, longitude 122°22'43"W. It is recommended that the charted advisory note regarding 4-foot depths be deleted and replaced with a 4-foot sounding and blue tins at latitude 37°40'10.5"N, longitude 122°22'41.7"W. This location is at the channel edge, however, the extent of this shoaling into the channel was not fully developed by the hydrographer. The charted 2-foot shoaling in the same channel was not confirmed and it is recommended that this note be removed from the chart. Two Foot depth from H9819/79 (VIA CL686/63). Channel obviously dredged since 1979 survey.

## d. Aids to Navigation

The following privately maintained aids to navigation were not investigated and are plotted from the DIP file for orientation purposes only.

Oyster Cove Marina Lights 1, 2, 11, 12, 13, 14, 16 Oyster Cove Marina Daybeacons 3, 4, 5, 6, 7, 8, 9, 10 The above aids to navigation mark the entrance channels to Oyster Cove Marina and Brisbane Marina (Sierra Point) and are located between latitude 37°40'12"N, longitude 122°22'39"W and latitude 37°40'04"N, longitude 122°23'09"W.

See section N, hydrographer's report, for aids located during this survey.

## e. Geographic Names

Names appearing on the smooth sheet and in the survey title have been approved by the Chief Geographer.

## f. Dangers to Navigation

The hydrographer reported five submerged obstructions and one submerged ruins to the USCG and N/CG222. Copies of the messages/reports are attached. No additional dangers were discovered during office processing.

#### 8. COMPLIANCE WITH INSTRUCTIONS

Survey FE-311 adequately complies with the Project Instructions.

## 9. ADDITIONAL FIELD WORK

This is a excellent field examination. Additional field work is requested by the California Department of Transportation upon removal of the submerged debris in the vicinity of the old Dumbarton Highway Bridge, latitude 37°30'16.70"N, longitude 122°07'07.32"W (see attached letters, dated February 5, 1988 and April 13, 1988).

C. R. Davies
Cartographer

This survey has been examined and it meets Charting and Geodetic Services' standards and requirements for use in nautical charting. Approval is recommended.

Dennis Hill

ami Hell

Chief, Hydrographic Section

## ATTACHMENT TO DESCRIPTIVE REPORT FOR FE-311

I have reviewed the smooth plots, accompanying data, and reports of this hydrographic survey. The hydrographic survey meets or exceeds Charting and Geodetic Services (C&GS) standards, complies with instructions, and is accurately and completely represented by the smooth plots and digital data file for use in nautical charting.

Chief, Nautical Chart Branch (Date)

CLEARANCE:

SIGNATURE AND DATE:

N/MOP2:LWMordock


After review of the smooth plots and accompanying reports, I hereby certify this survey is accurate, complete, and meets appropriate standards with only the exceptions as noted above. The above recommendations are forwarded with my concurrence.

Signand Rietersen 11/8/88 Director, Pacific Marine Center (Date)

## DEPARTMENT OF COMMERCE National Oceanic and Atmospheric Administration


National Ocean Survey Rockville, Maryland

Hydrographic Index No. 96M **INDEX** HYDROGRAPHIC SURVEYS Complete through November 1978 1971-1976 SAN FRANCISCO BAY AND VICINITY STOCKTON SACRAMENTO RIVER BODEG H-9660 HYDROGRAPHIC SURVEYS FARALLON ISLANDS FE-311 <u>Diagram</u> 5531-1





FE - 3 | I CALIFORNIA, SAN FRANCISCO BAY SOUTHERN PORTION OF SAN FRANCISCO BAY



37° 31′ 00″

37° 31' 00"

## FE - 311


## CALIFORNIA, SAN FRANCISCO BAY SOUTHERN PORTION OF SAN FRANCISCO BAY

Date of Survey: November 1987

Scale - 1:10,000

Soundings in FEET at MLLW

Item 188, AWOIS 51147 Investigations-Obstructions near Dumbarton Bridge Shareline in brown from Chart 1865) for orientation only



122922'30"

122 23 00

# MARINE CHART BRANCH RECORD OF APPLICATION TO CHARTS

FILE WITH DESCRIPTIVE REPORT OF SURVEY NO. FE-311

EXAMINED FOR NM

	INSTRUCTIONS				APPY	
	basic hydrographic or topographic survey supersedes all information of like nature on the uncorrected chart.				W .	
Letter all information. In "Remarks" column cross out words that do not apply.				11-6-89 P 11-6-89 P		
	s for deviations,	if any, from recommendations	made under "Comparison with Charts" in the Review.	· · · · · · · · · · · · · · · · · · ·		
CHART	DATE	CARTOGRAPHER	REMARKS	-		
18651	12-28-88	Con Only	Full Per Before After Marine Center Approval Signed Via			
100/1	1120	A COL	Drawing No 42 43 - Appled Date	which was one	12 4 5 h 100	
	1 0 4	THE THE STATE OF T		7		
MAN	19 6 61	Moment from also.	Full Part Before After Marine Center Approval Signed Via			
DE SO	17 5 5 1	Agmasy Timaskin	Drawing No.			
865ZA	11/9/95	MINU	Full Pas Defore After Marine Center Approval Signed Via			
0000	11/4/13	10/10	Drawing No. 32			
			Full Part Before After Marine Center Approval Signed Via	<u> </u>		
			Drawing No.	· · · · · · · · · · · · · · · · · · ·		
			Printing 1701	ŧ		
	<del>  -</del>		Full Part Before After Marine Center Approval Signed Via	·		
			Drawing No.			
	•		Diaming No.			
•			Full Part Before After Marine Center Approval Signed Via			
			Drawing No.			
	ļ		Diawing No.			
	<u> </u>		Full Part Before After Marine Center Approval Signed Via			
					<del></del>	
			Drawing No.			
			E II Dia Discus Africa Marine Center Americal Signed Vio			
			Full Part Before After Marine Center Approval Signed Via			
	1		Drawing No.			
			EUD-DG-AG-M-C-AG			
	<u> </u>		Full Part Before After Marine Center Approval Signed Via			
			Drawing No.			
		LANCE CONTROL OF THE PARTY OF T	Full Part Before After Marine Center Approval Signed Via			
			Drawing No.			
	<u> </u>					